

Project: : PROPOSED CONSTRUCTION OF 1000 CU.M. CYLINDRICAL GROUND STEEL TANK
 Location : PRK. CABUAY, BRGY. SINAWAL, GENERAL SANTOS CITY
 Owner : GENERAL SANTOS CITY WATER DISTRICT
 Subject : BILL OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
A	EARTH WORKS				
1.	Soil Investigation	1.00	sample		
2.	Earth Excavation	190.00	cu.m.		
3.	Gravel Beddings	34.00	cu.m.		
4.	Backfilling	424.20	cu.m.		
B.	CONCRETE WORKS				
1.	Steel Reinforcement	11,005.00	kgs.		
2.	Formworks & Scaffoldings	260.00	sq.m.		
3.	Concrete (3000 psi)	66.00	cu.m.		
4.	Asphalt	15.00	cu.m.		
5.	Catch Basin w/ Drainage line	110.00	l.m.		
6.	Valve Chamber	17.60	sq.m.		
C.	STEEL WORKS				
1.	Bottom Plates	10,500.00	kgs.		
2.	Shell Plates	26,856.28	kgs.		
3.	Roof Framing	4,787.42	kgs.		
4.	Roof Plate	5,819.10	kgs.		
5.	Railings and Ladder	3,800.88	kgs.		
6.	Manway	2.00	units		
7.	Sand Blasting	1,400.00	sq.m.		
D.	PIPING WORKS				
1.	Pipelines(Distribution, Overflow, Supply)	252.00	l.m.		
2.	500mmØ Butterfly Valve, F/F	1.00	set		
3.	200mmØ D.I. Gate Valve, F/F	2.00	sets		
4.	150mmØ D.I. Gate Valve, F/F	1.00	set		
5.	Water Level Indicator	1.00	set		
6.	Leak Testing & Disinfection	1,000.00	cu.m.		
E.	STUB-OUT				
1.	200mmØ with Gate Valve	1.00	set		
2.	200mmØ without Gate Valve	1.00	set		
F.	FITTINGS				
1.	500mmØ x 800mm Stainless Steel Strainer	1.00	set		
2.	500mmØ Fabricated Steel Bend	4.00	sets		
3.	250mmØ Fabricated Steel Bend	2.00	sets		

Project: : **PROPOSED CONSTRUCTION OF 1000 CU.M. CYLINDRICAL GROUND STEEL TANK**
 Location : **PRK. CABUAY, BRGY. SINAWAL, GENERAL SANTOS CITY**
 Owner : **GENERAL SANTOS CITY WATER DISTRICT**
 Subject : **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	4. 200mmØ Fabricated Steel Bend	4.00	sets		
G.	ELECTRICAL WORKS				
	1. Wirings & Fixtures	1.00	l.s.		
H.	PAINTING WORKS				
	1. Concrete & Steel Painting	1.00	l.s.		
I.	SPECIAL ITEMS				
	1. Provision of Field Office for Resident Engineer	1.00	lot		
	2. Project Signboard (GSCWD and COA)	2.00	sets		
	3. Occupation Safety and Health Program	1.00	lot		
	4. Mobilization and Demobilization	1.00	lot		
	TOTAL PROJECT COST				

Submitted by

Date: _____

Name of representative of Bidder : _____

Position: _____

Name of Bidder : _____