



Republic of the Philippines

GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St., Brgy. Lagao, General Santos City

Telephone No.: 552-3824; Telefax No.: 553-4960

Email Address: gscwaterdistrict@yahoo.com

Project: **RENOVATION AND IMPROVEMENT OF OLD WAREHOUSE INTO HRD TRAINING HALL**

Location: **GSCWD COMPOUND, E. FERNANDEZ ST., LAGAO, GSC**

Owner: **GENERAL SANTOS CITY WATER DISTRICT**

Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1	MOBILIZATION				
1.a	MOBILIZATION	1.00	L.S.		
2	REMOVAL/DEMOLITION OF STRUCTURES AND OBSTRUCTIONS				
2.a	Demolition and removal of existing office, cabinets, tables, existing wooden partitions, existing doors and windows, window grill, racks and other obstruction including demolition of walls for windows and doors provisions.	1.00	L.S.		
3	INDIVIDUAL REMOVAL OF TREES, 200mmØ				
3.a	Removal and disposal of 9-palm trees 200mmØ	9.00	EA		
4	Concrete Cutting and demolition of pavement				
4.a	Concrete Cutting and demolition of pavement	1.00	L.S.		
5	EARTHWORKS				
5.a	Earth Excavation	27.00	CU.M.		
5.b	Gravel Bedding	20.00	CU.M.		
5.c	Backfilling and Compaction	73.00	CU.M.		
6	MASONRY WORKS				
6.a	(EXISTING DOORS, WINDOWS AND WALL PARTITION OPENING) Furnishing and Installation of 4" CHB including reinforcing steel, plastered both sides, smooth finished on doors, windows, and wall partitions opening.	100.00	SQ.M.		
6.b	(EXISTING DOORS, WINDOWS AND WALL PARTITION OPENING) Furnishing and Installation of 4" CHB including reinforcing steel, plastered both sides, smooth finished on doors, windows, and wall partitions opening.	42.00	SQ.M.		
6.c	CEMENT PLASTER FINISH OF EXISTING CHB WALL	400.00	SQ.M.		
7	STRUCTURAL CONCRETE (CLASS "A")				

7.a	Concrete Works with Compressive strength of 21 Mpa(3000psi) @ 28 days	20.00	CU.M.		
8	REINFORCING STEEL (DEFORMED)				
8.a	Furnishing and installation of reinforcing	360.00	KGS		
9	PREPAINTED METAL SHEETS (LONG SPAN,				
9.a	Furnishing and Installation of Rib-Type Long Span Pre-painted Roofing, 0.40mm thk x 1.05 effective width.	266.00	L.M.		
10	PRE-PAINTED PREFORMED G.I. GUTTER				
10.a	Furnishing and installation of Preformed G.I. Gutter and Preformed Pre-painted G.I. End Flashing, 0.60mm thk., including its accessories	20.00	L.M.		
11	CEILING WORKS				
11.a	Furnishing and Installation of Ceiling, 3.5mm thk. Fiber Cement Board, paint finished including its metal furring ceiling frames refer to approved plan.	230.00	SQ.M.		
12	TILE WORKS				
12.a	Furnishing and Installation of Assorted Tiles	163.00	SQ.M.		
13	DOORS				
13.a	Furnishing and Installation of PVC Toilet Doors w/ complete accessories	2.00	SETS		
13.b	Furnishing and Installation of 40mm thk x 0.80m x 2.10m Panel Door Type in 50 x 150 KD Door Jamb Paint Finish with complete accessories	1.00	SET		
13.c	Furnishing and Installation of two-way double swing door and two-way swing glass door, in powder coated finish aluminum framed w/ 10mm thk tinted glass panels (Materials, fabrication, & installation)	2.00	SETS		
13.d	Furnishing and Installation of fixed windows in powder coated finish aluminum frame with 6mm thk tinted glass panel with complete accessories (Materials, fabrication, & installation)	4.00	SETS		
13.e	Furnishing and Installation of sliding window in powder coated finish aluminum frame with 6mm thk tinted glass panel with complete accessories (Materials, fabrication, & installation)	1.00	SET		

13.f	Furnishing and Installation of awning window in powder coated finish aluminum frame with 6mm thk tinted glass panel with complete accessories (Materials, fabrication, & installation)	2.00	SETS		
14	FABRICATED OPERABLE WALL PARTITION				
14.a	Furnishing and Installation of Operable soundproof wall partition full fabric with 5cm thickness aluminum frame powder coated with adjustable railing tubular/roller track/roller guide and header with rackwool	1.00	SET		
15	PLUMBING WORKS				
15.a	DRAINAGE AND SEWER LINE WORKS	1.00	L.S.		
15.b	COLD WATER LINES	1.00	L.S.		
15.c	PLUMBING FIXTURES	1.00	L.S.		
16	ELECTRICAL WORKS				
16.a	CONDUIT WORKS/CONDUIT ROUGH-IN	1.00	L.S.		
16.b	WIRES AND WIRING DEVICES	1.00	L.S.		
16.c	PANEL BOARD AND MAIN BREAKER	1.00	L.S.		
16.d	LIGHTING FIXTURE AND LAMPS	1.00	L.S.		
17	PAINTING WORKS (WOOD)				
17.a	PAINTING (MASONRY/CONCRETE)	550.00	SQ.M.		
17.b	PAINTING WORKS (WOOD)	230.00	SQ.M.		
18	FORMWORKS AND SCAFFOLDING				
18.a	FORMWORKS AND SCAFFOLDING	1.00	L.S.		
19	SPECIAL ITEMS				
19.a	Project Signboard	1.00	SET		
19.b	COA Project Signboard	1.00	SET		
19.c	Occupational Safety and Health Program	1.00	L.S.		
20	Demobilization				
20.a	Demobilization	1.00	L.S.		
TOTAL PROJECT COST		-			

NOTE:

PLEASE REFER TO SPECIFICATION FOR FURTHER DETAILS

Submitted by

Date: _____

Name of representative of Bic : _____

Position: _____

Name of Bidder : _____

Issued on :