



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St., Brgy. Lagao, General Santos City
 Telephone No.: 552-3824; Telefax No.: 553-4960
 Email Address: gscwaterdistrict@yahoo.com

Project: **PROPOSED CONSTRUCTION OF LIFTING STRUCTURE FRAME**

Location: **LOT 6, PS No.5, PUROK RIVERSIDE, SAN ISIDRO, GSC**

Owner: **GENERAL SANTOS CITY WATER DISTRICT**

Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1	MOBILIZATION				
1.a	Mobilization	1.00	lot		
2	Concrete Cutting and demolition of pavement	1.00	lot		
3	EARTHWORKS				
3.a	Earth Excavation	7.00	cu.m.		
3.b	Gravel Bedding	1.00	cu.m.		
3.c	Backfilling and Compaction	7.00	cu.m.		
4	STRUCTURAL CONCRETE (CLASS "A")				
4.a	Concrete Works with Compressive strength of 21 Mpa(3000psi) @ 28 days	2.00	cu.m		
5	REINFORCING STEEL				
5.a	Furnishing and installation of reinforcing steel bars	185.00	kgs		
6	STRUCTURAL STEEL WORKS				
6.a	Furnishing and Installation of W6 x 9 and W8 x 24 Wide Flange Column and Beams (Paint finish), including 75mm x 75mm x 6mm thk. Angle bar Diagonal Member (Paint finish)	1,456.00	kgs.		
6.b	Furnishing and Installation of Stiffener plate, base plate, gusset plate, & anchor plate (Paint finish)	433.00	kgs.		
6.c	Furnishing and Installation of 1 1/4"Ø sch.40 G.I. pipe railings (Paint finish)	8.00	lin.m.		
6.d	Furnishing and Installation of 12mmØ x 6.00m Plain Round Bar Railings, MS (Paint finish)	167.00	kgs		
6.e	Furnishing and Installation of 12mmØ x 6.00m Plain Round Bar Work Platform, MS (Paint finish)	76.00	kgs		
6.f	Furnishing and Installation of 50mm x 50mm x 6mm thk. Angle Bar Work Platform Support (Paint finish)	430.00	kgs.		
6.g	Furnishing and Installation of Ladder and ladder safety cage (Paint finish)	155.00	kgs.		
6.h	Furnishing and Installation of 20mmØ x 400mm Anchor bolts with nut and plain washers at both end	24.00	sets		

7	PAINTING				
7.a	Painting Works (STEEL)	1.00	lot		
8	FORMWORKS AND SCAFFOLDING				
8.a	Formworks and Scaffolding	1.00	lot		
9	SPECIAL ITEMS				
9.a	Project Signboard	1.00	set		
9.b	COA Project Signboard	1.00	set		
9.c	Occupational Safety and Health Program	1.00	lot		
10	DEMOBILIZATION				
10.a	Demobilization	1.00	lot		
	TOTAL PROJECT COST	-			

NOTE:

PLEASE REFER TO SPECIFICATION FOR FURTHER DETAILS

Submitted by

Date: _____

Name of representative of Bic : _____

Position: _____

Name of Bidder : _____

Issued on :