



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Legaspi, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: USED OIL SHED - 4 NOS.
 Location: CLUSTER 1 - PUMPSTATION NO. 1, 2, 4, AND 5 (BRGY. SAN ISIDRO, GSC)
 Owner: GENERAL SANTOS CITY WATER DISTRICT
 Subject: BILL OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
USED OIL SHED - 4 NOS.					
A.1	EXCAVATION				
B.1.1	Excavation of Column Footing	8	CU.M.		
A.2	GRAVEL BEDDING				
B.2.1	Furnishing and Gravel Bedding of Column Footing and Slab on Grade	4	CU.M.		
A.3	BACKFILLING AND COMPACTION				
B.3.1	Backfilling and Compaction of Column Footing and Wall Footing	5	CU.M.		
B.1	REBARWORKS				
B.1.1	Furnishing and Installation of 10mm and 12mm dia. Deformed bars for Column and Slab rebars	412	KGS.		
B.2	FALSEWORKS & CONCRETE WORKS				
B.2.1	Concreting of Column Footing, Column and Slab with 3000psi - Class A Mixture	6	CU.M.		
B.2.2	Furnishing and Installation of Falseworks	4	NOS.		
C.1	STEEL FRAMING WORKS				
STEEL FRAMING WORKS					
C.1.1	Furnishing and Installation of 3" GI Pipe Schedule 40	8	LENGTH		
C.1.2	Furnishing and Installation of 150mm x 50mm x 1.5mm Thickness Steel Tubular	8	LENGTH		
C.1.3	Furnishing and Installation of 100mm x 50mm x 1.5mm Thickness Steel Tubular	8	LENGTH		
C.1.4	Furnishing and Installation of 75mm x 50mm x 1.5mm Thickness C - Purlins	24	LENGTH		
STEEL DRUM					
C.1.5	Furnishing of Closed Top Drum - 210L, 2" x 3/4" plugs with Black Nitrile Washer (for Used Oil), Black Paint Color with label	12	NOS.		



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gsowaterdistrict@yahoo.com

Project: **USED OIL SHED - 4 NOS.**
 Location: **CLUSTER 1 - PUMPSTATION NO. 1, 2, 4, AND 5 (BRGY. SAN ISIDRO, GSC)**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
C.1.6	<i>Furnishing of Open Top Drum - 210L, Lever Action Ring (for Used Oil Filters, Waste electrical and electronic equipment (WEEE), Oil contaminated), Black Paint Color with label</i>	8	NOS.		
C.1.7	<i>Furnishing of Open Top Drum - 210L, Lever Action Ring (for Biodegradable), Green Paint Color with label</i>	4	NOS.		
C.1.8	<i>Furnishing of Open Top Drum - 210L, Lever Action Ring (for Recyclable), Blue Paint Color with label</i>	8	NOS.		
C.2	ROOFING WORKS				
C.2.1	<i>Furnishing and Installation of Rib Type Long Span Pre-Pointed Roofing, 0.4mm thk</i>	61	LM		
C.2.2	<i>Furnishing and Installation of Tekscrew (2 1/2")</i>	400	NOS.		
C.3	PAINTING WORKS				
C.3.1	<i>Furnishing and Application of Epoxy Primer Paint</i>	4	LITER		
C.3.2	<i>Furnishing and Application of Epoxy Enamel Paint</i>	4	LITER		
C.3.3	<i>Furnishing and Application of Epoxy Reducer</i>	4	LITER		
C.3.4	<i>Furnishing and Application of Elastomeric Sealant - 0.50L</i>	4	1/2 LITER		
Total Project Cost					

Note:

PLEASE REFER TO APPROVED PLAN FOR FURTHER DETAILS

Submitted by _____ Date: _____
 Name of representative of Bidder _____
 Position: _____
 Name of Bidder _____



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
 E. Fernandez St. Laga, General Santos City
 Telephone No. (083) 552-8824/ Telefax No. (083) 553-4900
 E-mail Address: gscwaterdistrict@yahoo.com

Project: USED OIL SHED - 2 NOS.
 Location: CLUSTER 2 - PUMPSTATION NO. 9 AND 20 (BRGY. CALUMPANG SYSTEM)
 Owner: GENERAL SANTOS CITY WATER DISTRICT
 Subject: BILL OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
USED OIL SHED - 2 NOS.					
A.1	EXCAVATION				
B.1.1	Excavation of Column Footing	4	CU.M.		
A.2	GRAVEL BEDDING				
B.2.1	Furnishing and Gravel Bedding of Column Footing and Slab on Grade	2	CU.M.		
A.3	BACKFILLING AND COMPACTION				
B.3.1	Backfilling and Compaction of Column Footing and Wall Footing	2	CU.M.		
B.1	REBARWORKS				
B.1.1	Furnishing and Installation of 10mm and 12mm dia. Deformed bars for Column and Slab rebars	206	KGS.		
B.2	FALSEWORKS & CONCRETE WORKS				
B.2.1	Concreting of Column Footing, Column and Slab with 3000psi - Class A Mixture	3	CU.M.		
B.2.2	Furnishing and Installation of Falseworks	2	NOS.		
C.1	STEEL FRAMING WORKS				
STEEL FRAMING WORKS					
C.1.1	Furnishing and Installation of 3" GI Pipe Schedule 40	4	LENGTH		
C.1.2	Furnishing and Installation of 150mm x 50mm x 1.5mm Thickness Steel Tubular	4	LENGTH		
C.1.3	Furnishing and Installation of 100mm x 50mm x 1.5mm Thickness Steel Tubular	4	LENGTH		
C.1.4	Furnishing and Installation of 75mm x 50mm x 1.5mm Thickness C - Purlins	12	LENGTH		
STEEL DRUM					
C.1.5	Furnishing of Closed Top Drum - 210L, 2" x 3/4" plugs with Black Nitrile Washer (for Used Oil), Black Paint Color with label	6	NOS.		



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3874/ Telefax No. (083) 553-1960
 E-mail Address: gswaterdistrict@yahoo.com

Project: **USED OIL SHED - 2 NOS.**
 Location: **CLUSTER 2 - PUMPSTATION NO. 9 AND 20 (BRGY. CALUMPANG SYSTEM)**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
C.1.6	<i>Furnishing of Open Top Drum - 210L, Lever Action Ring (for Used Oil Filters, Waste electrical and electronic equipment (WEEE), Oil contaminated), Black Paint Color with label</i>	4	NOS.		
C.1.7	<i>Furnishing of Open Top Drum - 210L, Lever Action Ring (for Biodegradable), Green Paint Color with label</i>	2	NOS.		
C.1.8	<i>Furnishing of Open Top Drum - 210L, Lever Action Ring (for Recyclable), Blue Paint Color with label</i>	4	NOS.		
C.2	ROOFING WORKS				
C.2.1	<i>Furnishing and Installation of Rib Type Long Span Pre-Painted Roofing, 0.4mm thk</i>	30	LM		
C.2.2	<i>Furnishing and Installation of Tekscrew (2 1/2")</i>	200	NOS.		
C.3	PAINTING WORKS				
C.3.1	<i>Furnishing and Application of Epoxy Enamel Paint</i>	2	LITER		
C.3.2	<i>Furnishing and Application of Epoxy Enamel Paint</i>	2	LITER		
C.3.3	<i>Furnishing and Application of Epoxy Reducer</i>	2	LITER		
C.3.4	<i>Furnishing and Application of Elastomeric Sealant - 0.50L</i>	2	1/2 LITER		
Total Project Cost					

Note:

PLEASE REFER TO APPROVED PLAN FOR FURTHER DETAILS

Submitted by _____ : _____

Date: _____

Name of representative of Bidder _____ : _____

Position: _____ : _____

Name of Bidder _____ : _____



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagoo, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: USED OIL SHED - 4 NOS.
 Location: CLUSTER 3 - PUMPSTATION NO. 10, 12, 21 AND 24 (BRGY. FATIMA SYSTEM)
 Owner: GENERAL SANTOS CITY WATER DISTRICT
 Subject: BILL OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
USED OIL SHED - 4 NOS.					
A.1	EXCAVATION				
B.1.1	Excavation of Column Footing	8	CU.M.		
A.2	GRAVEL BEDDING				
B.2.1	Furnishing and Gravel Bedding of Column Footing and Slab on Grade	4	CU.M.		
A.3	BACKFILLING AND COMPACTION				
B.3.1	Backfilling and Compaction of Column Footing and Wall Footing	5	CU.M.		
B.1	REBARWORKS				
B.1.1	Furnishing and Installation of 10mm and 12mm dia. Deformed bars for Column and Slab rebars	412	KGS.		
B.2	FALSEWORKS & CONCRETE WORKS				
B.2.1	Concreting of Column Footing, Column and Slab with 3000psi - Class A Mixture	6	CU.M.		
B.2.2	Furnishing and Installation of Falseworks	4	LOT		
C.1	STEEL FRAMING WORKS				
	STEEL FRAMING WORKS				
C.1.1	Furnishing and Installation of 3" GI Pipe Schedule 40	8	LENGTH		
C.1.2	Furnishing and Installation of 150mm x 50mm x 1.5mm Thickness Steel Tubular	8	LENGTH		
C.1.3	Furnishing and Installation of 100mm x 50mm x 1.5mm Thickness Steel Tubular	8	LENGTH		
C.1.4	Furnishing and Installation of 75mm x 50mm x 1.5mm Thickness C - Purlins	24	LENGTH		
	STEEL DRUM				
C.1.5	Furnishing of Closed Top Drum - 210L, 2" x 3/4" plugs with Black Nitrile Washer (for Used Oil), Black Paint Color with label	12	NOS.		



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagon, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4060
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **USED OIL SHED - 4 NOS.**
 Location: **CLUSTER 3 - PUMPSTATION NO. 10, 12, 21 AND 24 (BRGY. FATIMA SYSTEM)**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
C.1.6	<i>Furnishing of Open Top Drum - 210L, Lever Action Ring (for Used Oil Filters, Waste electrical and electronic equipment (WEEE), Oil contaminated), Black Paint Color with label</i>	8	NOS.		
C.1.7	<i>Furnishing of Open Top Drum - 210L, Lever Action Ring (for Biodegradable), Green Paint Color with label</i>	4	NOS.		
C.1.8	<i>Furnishing of Open Top Drum - 210L, Lever Action Ring (for Recyclable), Blue Paint Color with label</i>	8	NOS.		
C.2	ROOFING WORKS				
C.2.1	<i>Furnishing and Installation of Rib Type Lang Span Pre-Painted Roofing, 0.4mm thk</i>	61	LM		
C.2.2	<i>Furnishing and Installation of Tekscrew (2 1/2")</i>	400	NOS.		
C.3	PAINTING WORKS				
C.3.1	<i>Furnishing and Application of Epoxy Primer Paint</i>	4	LITER		
C.3.2	<i>Furnishing and Application of Epoxy Enamel Paint</i>	4	LITER		
C.3.3	<i>Furnishing and Application of Epoxy Reducer</i>	4	LITER		
C.3.4	<i>Furnishing and Application of Elastomeric Sealant - 0.50L</i>	4	1/2 LITER		
Total Project Cost					

Note:

PLEASE REFER TO APPROVED PLAN FOR FURTHER DETAILS

Submitted by _____ :

Date: _____

Name of representative of Bidder _____ :

Position: _____ :

Name of Bidder _____ :



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

F. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552 3824/ Telefax No. (083) 553-4960
 E mail Address: gscwaterdistrict@yahoo.com

Project: **USED OIL SHED - 5 NOS.**
 Location: **CLUSTER 4 - PUMPSTATION NO. 6, 7, 8, 22 AND 26 (BRGY. SINAWAL AND APOPONG SYSTEM)**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
USED OIL SHED - 5 NOS.					
A.1	EXCAVATION				
B.1.1	<i>Excavation of Column Footing</i>	10	CU.M.		
A.2	GRAVEL BEDDING				
B.2.1	<i>Furnishing and Gravel Bedding of Column Footing and Slab on Grade</i>	5	CU.M.		
A.3	BACKFILLING AND COMPACTION				
B.3.1	<i>Backfilling and Compaction of Column Footing and Wall Footing</i>	6	CU.M.		
B.1	REBARWORKS				
B.1.1	<i>Furnishing and Installation of 10mm and 12mm dia. Deformed bars for Column and Slab rebars</i>	514	KGS.		
B.2	FALSEWORKS & CONCRETE WORKS				
B.2.1	<i>Concreting of Column Footing, Column and Slab with 3000psi - Class A Mixture</i>	7	CU.M.		
B.2.2	<i>Furnishing and Installation of Falseworks</i>	5	NOS.		
C.1	STEEL FRAMING WORKS				
STEEL FRAMING WORKS					
C.1.1	<i>Furnishing and Installation of 3" GI Pipe Schedule 40</i>	10	LENGTH		
C.1.2	<i>Furnishing and Installation of 150mm x 50mm x 1.5mm Thickness Steel Tubular</i>	10	LENGTH		
C.1.3	<i>Furnishing and Installation of 100mm x 50mm x 1.5mm Thickness Steel Tubular</i>	10	LENGTH		
C.1.4	<i>Furnishing and Installation of 75mm x 50mm x 1.5mm Thickness C - Purlins</i>	30	LENGTH		
STEEL DRUM					
C.1.5	<i>Furnishing of Closed Top Drum - 210L, 2" x 3/4" plugs with Black Nitrile Washer (for Used Oil), Black Paint Color with label</i>	15	NOS.		



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
 E. Fernandez St. Lagoo, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-1960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **USED OIL SHED - 5 NOS.**
 Location: **CLUSTER 4 - PUMPSTATION NO. 6, 7, 8, 22 AND 26 (BRGY. SINAWAL AND APOPONG SYSTEM)**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
C.1.6	<i>Furnishing of Open Top Drum - 210L, Lever Action Ring (for Used Oil Filters, Waste electrical and electronic equipment (WEEE), Oil contaminated), Black Paint Color with label</i>	10	NOS.		
C.1.7	<i>Furnishing of Open Top Drum - 210L, Lever Action Ring (for Biodegradable), Green Paint Color with label</i>	5	NOS.		
C.1.8	<i>Furnishing of Open Top Drum - 210L, Lever Action Ring (for Recyclable), Blue Paint Color with label</i>	10	NOS.		
C.2	ROOFING WORKS				
C.2.1	<i>Furnishing and Installation of Rib Type Long Span Pre-Painted Roofing, 0.4mm thk</i>	76	LM		
C.2.2	<i>Furnishing and Installation of Tekscrew (2 1/2")</i>	500	NOS.		
C.3	PAINTING WORKS				
C.3.1	<i>Furnishing and Application of Epoxy Primer Paint</i>	5	LITER		
C.3.2	<i>Furnishing and Application of Epoxy Enamel Paint</i>	5	LITER		
C.3.3	<i>Furnishing and Application of Epoxy Reducer</i>	5	LITER		
C.3.4	<i>Furnishing and Application of Elastomeric Sealant - 0.50L</i>	5	1/2 LITER		
Total Project Cost					

Note:

PLEASE REFER TO APPROVED PLAN FOR FURTHER DETAILS

Submitted by _____ Date: _____
 Name of representative of Bidder _____
 Position: _____
 Name of Bidder _____



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

F. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **USED OIL SHED - 2 NOS.**
 Location: **CLUSTER 5 - PUMPSTATION NO. 14, 15 AND 17 (BRGY. MABUHAY SYSTEM)**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
USED OIL SHED - 2 NOS.					
A.1	EXCAVATION				
	B.1.1 Excavation of Column Footing	4	CU.M.		
A.2	GRAVEL BEDDING				
	B.2.1 Furnishing and Gravel Bedding of Column Footing and Slab on Grade	2	CU.M.		
A.3	BACKFILLING AND COMPACTION				
	B.3.1 Backfilling and Compaction of Column Footing and Wall Footing	2	CU.M.		
B.1	REBARWORKS				
	B.1.1 Furnishing and Installation of 10mm and 12mm dia. Deformed bars for Column and Slab rebars	206	KGS.		
B.2	FALSEWORKS & CONCRETE WORKS				
	B.2.1 Concreting of Column Footing, Column and Slab with 3000psi Class A Mixture	3	CU.M.		
	B.2.2 Furnishing and Installation of Falseworks	2	NOS.		
C.1	STEEL FRAMING WORKS				
	C.1.1 Furnishing and Installation of 3" GI Pipe Schedule 40	4	LENGTH		
	C.1.2 Furnishing and Installation of 150mm x 50mm x 1.5mm Thickness Steel Tubular	4	LENGTH		
	C.1.3 Furnishing and Installation of 100mm x 50mm x 1.5mm Thickness Steel Tubular	4	LENGTH		
	C.1.4 Furnishing and Installation of 75mm x 50mm x 1.5mm Thickness C - Purlins	12	LENGTH		
STEEL DRUM					
	C.1.5 Furnishing of Closed Top Drum - 210L, 2" x 3/4" plugs with Black Nitrile Washer (for Used Oil), Black Paint Color with label	6	NOS.		
	C.1.6 Furnishing of Open Top Drum - 210L, Lever Action Ring (for Used Oil Filters, Waste electrical and electronic equipment (WEEE), Oil contaminated), Black Paint Color with label	4	NOS.		



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Legaspi, General Santos City
 Telephone No. (083) 552 3824/ Telefax No. (083) 553 4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **USED OIL SHED - 2 NOS.**
 Location: **CLUSTER 5 - PUMPSTATION NO. 14, 15 AND 17 (BRGY. MABUHAY SYSTEM)**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
C.1.7	Furnishing of Open Top Drum - 210L, Lever Action Ring (for Biodegradable), Green Paint Color with label	2	NOS.		
C.1.8	Furnishing of Open Top Drum - 210L, Lever Action Ring (for Recyclable), Blue Paint Color with label	4	NOS.		
C.2	ROOFING WORKS				
C.2.1	Furnishing and Installation of Rib Type Long Span Pre-Painted Roofing, 0.4mm thk	30	LM		
C.2.2	Furnishing and Installation of Tek screw (2 1/2")	200	NOS.		
C.3	PAINTING WORKS				
C.3.1	Furnishing and Application of Epoxy Primer Paint	2	LITER		
C.3.2	Furnishing and Application of Epoxy Enamel Paint - Grey	2	LITER		
C.3.3	Furnishing and Application of Epoxy Reducer	2	LITER		
C.3.4	Furnishing and Application of Elastomeric Sealant - 0.50L	2	1/2 LITER		
	Total Project Cost				

Note:

PLEASE REFER TO APPROVED PLAN FOR FURTHER DETAILS

Submitted by _____ Date: _____
 Name of representative of Bidder _____
 Position: _____
 Name of Bidder _____



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagan, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gswaterdistrict@yahoo.com

Project: **USED OIL SHED - 3 NOS.**
 Location: **CLUSTER 6 - PUMPSTATION NO. 16, 19, 23 AND 25 (BRGY. CONEL AND SAN ISIDRO SYSTEM)**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
USED OIL SHED - 3 NOS.					
A.1	EXCAVATION				
	B.1.1 <i>Excavation of Column Footing</i>	7	CU.M.		
A.2	GRAVEL BEDDING				
	B.2.1 <i>Furnishing and Gravel Bedding of Column Footing and Slab on Grade</i>	4	CU.M.		
A.3	BACKFILLING AND COMPACTION				
	B.3.1 <i>Backfilling and Compaction of Column Footing and Wall Footing</i>	4	CU.M.		
B.1	REBARWORKS				
	B.1.1 <i>Furnishing and Installation of 10mm and 12mm dia. Deformed bars for Column and Slab rebars</i>	345	KGS.		
B.2	FALSEWORKS & CONCRETE WORKS				
	B.2.1 <i>Concreting of Column Footing, Column and Slab with 3000psi - Class A Mixture</i>	6	CU.M.		
	B.2.2 <i>Furnishing and Installation of Falseworks</i>	3	NOS.		
C.1	STEEL FRAMING WORKS				
	C.1.1 <i>Furnishing and Installation of 3" GI Pipe Schedule 40</i>	8	LENGTH		
	C.1.2 <i>Furnishing and Installation of 150mm x 50mm x 1.5mm Thickness Steel Tubular</i>	8	LENGTH		
	C.1.3 <i>Furnishing and Installation of 100mm x 50mm x 1.5mm Thickness Steel Tubular</i>	8	LENGTH		
	C.1.4 <i>Furnishing and Installation of 75mm x 50mm x 1.5mm Thickness C- Purlins</i>	24	LENGTH		
	STEEL DRUM				
	C.1.5 <i>Furnishing of Closed Top Drum - 210L, 2" x 3/4" plugs with Black Nitrile Washer (for Used Oil), Black Paint Color with label</i>	11	NOS.		
	C.1.6 <i>Furnishing of Open Top Drum - 210L, Lever Action Ring (for Used Oil Filters, Waste electrical and electronic equipment (WEEE), Oil contaminated), Black Paint Color with label</i>	14	NOS.		



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: USED OIL SHED - 3 NOS.
 Location: CLUSTER 6 - PUMPSTATION NO. 16, 19, 23 AND 25 (BRGY. CONEL AND SAN ISIDRO SYSTEM)
 Owner: GENERAL SANTOS CITY WATER DISTRICT
 Subject: BILL OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
C.1.7	Furnishing of Open Top Drum - 210L, Lever Action Ring (for Biodegradable), Green Paint Color with label	3	NOS.		
C.1.8	Furnishing of Open Top Drum - 210L, Lever Action Ring (for Recyclable), Blue Paint Color with label	6	NOS.		
C.2	ROOFING WORKS				
C.2.1	Furnishing and Installation of Rib Type Long Span Pre-Painted Roofing, 0.4mm thk	61	LM		
C.2.2	Furnishing and Installation of Tekscrew (2 1/2")	400	NOS.		
C.3	PAINTING WORKS				
C.3.1	Furnishing and Application of Epoxy Primer Paint	4	LITER		
C.3.1	Furnishing and Application of Epoxy Enamel Paint	4	LITER		
C.3.2	Furnishing and Application of Epoxy Reducer	4	LITER		
C.3.3	Furnishing and Application of Elastomeric Sealant - 0.50L	4	1/2 LITER		
Total Project Cost					

Note:

PLEASE REFER TO APPROVED PLAN FOR FURTHER DETAILS

Submitted by _____ Date: _____
 Name of representative of Bidder _____
 Position: _____
 Name of Bidder _____



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagan, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553 4860
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **USED OIL SHED - 1 NO.**
 Location: **CLUSTER 7 - PUMPSTATION NO. 18 (BRGY. SAN JOSE SYSTEM)**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
USED OIL SHED - 1 NO.					
A.1	EXCAVATION				
B.1.1	Excavation of Column Footing	2	CU.M.		
A.2	GRAVEL BEDDING				
B.2.1	Furnishing and Gravel Bedding of Column Footing and Slab on Grade	1	CU.M.		
A.3	BACKFILLING AND COMPACTION				
B.3.1	Backfilling and Compaction of Column Footing and Wall Footing	1	CU.M.		
B.1	REBARWORKS				
B.1.1	Furnishing and Installation of 10mm and 12mm dia. Deformed bars for Column and Slab rebars	103	KG5.		
B.2	FALSEWORKS & CONCRETE WORKS				
B.2.1	Concreting of Column Footing, Column and Slab with 3000psi - Class A Mixture	1	CU.M.		
B.2.2	Furnishing and Installation of Falseworks	2	LOT		
C.1	STEEL FRAMING WORKS				
C.1.1	Furnishing and Installation of 3" Gi Pipe Schedule 40	2	LENGTH		
C.1.2	Furnishing and Installation of 150mm x 50mm x 1.5mm Thickness Steel Tubular	2	LENGTH		
C.1.3	Furnishing and Installation of 100mm x 50mm x 1.5mm Thickness Steel Tubular	2	LENGTH		
C.1.4	Furnishing and Installation of 75mm x 50mm x 1.5mm Thickness C - Purlins	6	LENGTH		
STEEL DRUM					
C.1.5	Furnishing of Closed Top Drum - 210L, 2" x 3/4" plugs with Black Nitrile Washer (for Used Oil), Black Paint Color with label	3	NOS.		
C.1.6	Furnishing of Open Top Drum - 210L, Lever Action Ring (for Used Oil Filters, Waste electrical and electronic equipment (WEEE), Oil contaminated), Black Paint Color with label	2	NOS.		



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
 F. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552 8824/ Telefax No. (083) 553-1900
 E-mail Address: gswaterdistrict@yahoo.com

Project: **USED OIL SHED - 1 NO.**
 Location: **CLUSTER 7 - PUMPSTATION NO. 18 (BRGY. SAN JOSE SYSTEM)**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
C.1.7	<i>Furnishing of Open Top Drum - 210L, Lever Action Ring (for Biodegradable), Green Paint Color with label</i>	1	NOS.		
C.1.8	<i>Furnishing of Open Top Drum - 210L, Lever Action Ring (for Recyclable), Blue Paint Color with label</i>	2	NOS.		
C.2	ROOFING WORKS				
C.2.1	<i>Furnishing and Installation of Rib Type Long Span Pre Painted Roofing, 0.4mm thk</i>	15	LM		
C.2.2	<i>Furnishing and Installation of Tekscrew (2 1/2")</i>	100	NOS.		
C.3	PAINTING WORKS				
C.3.1	<i>Furnishing and Application of Epoxy Primer Paint</i>	1	LITER		
C.3.1	<i>Furnishing and Application of Epoxy Enamel Paint</i>	1	LITER		
C.3.2	<i>Furnishing and Application of Epoxy Reducer</i>	1	LITER		
C.3.3	<i>Furnishing and Application of Elastomeric Sealant - 0.50L</i>	1	1/2 LITER		
Total Project Cost					

Note:

PLEASE REFER TO APPROVED PLAN FOR FURTHER DETAILS

Submitted by _____ Date: _____
 Name of representative of Bidder _____
 Position: _____
 Name of Bidder _____