



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **REHABILITATION OF 1,500 CUBIC METER CYLINDRICAL GROUND STEEL TANK**
 Location: **SM VILLAGE, BRGY. SINAWAL, GENERAL SANTOS CITY**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

| ITEM NO. | DESCRIPTION | QUANTITY | UNIT | UNIT COST | AMOUNT |
|----------|--|----------|------|-----------|--------|
| A | STEEL WORKS | | | | |
| A.1 | Scrapping & Re-welding of Bottom Plate | 1.00 | lot | | |
| a.1a. | <i>Scrapping (Paint Removal) & Re-welding of Doupler Plate</i> | | | | |
| A.2 | Removal of Existing Roof Plate and Framing and Installation of Roof Checkered Plate | 4,263.55 | kgs. | | |
| a.2a. | <i>Removal of existing roof plate & framing</i> | | | | |
| a.2b. | <i>Furnishing & Installation of 4' x 8' x 3.0mm thk. Stainless Steel Checkered Plate (304)</i> | | | | |
| A.3 | Roof Framing | 4,400.87 | kgs. | | |
| a.3a. | <i>Furnishing & Installation of Stainless Steel Trusses (304) in Accordance with the approved plan.</i> | | | | |
| a.3b. | <i>Furnishing & Installation of 50mmx 100mm x 1.2 mm thk. Stainless steel rectangular tubing including 10mmØ stainless steel PRB Sagrads (304).</i> | | | | |
| a.3c. | <i>Furnishing & Installation of additional one (2) unit 200mm(8")Ø Galvanized Steel Air Vent with Stainless Steel Bird Screen and its accessories.</i> | | | | |
| a.3d. | <i>Furnishing & Installation of 14"Ø x 1.0m B.I. Pipe, Sched. 80 (Center Connector).</i> | | | | |
| a.3e. | <i>Furnishing & Installation of 8"Ø B.I. Pipe, Sched. 80 (Center Column).</i> | | | | |
| A.4 | ROOF HANDRAILS | 610.62 | kgs. | | |
| a.4a. | <i>Furnishing & Installation of Roof Handrails in Accordance with the approved plan.</i> | | | | |
| A.5 | ROOF MANWAY | 1.00 | unit | | |
| a.5a. | <i>Furnishing & Installation of Roof manway</i> | | | | |
| B | WATER LEVEL INDICATOR WORKS | | | | |
| B.1 | Water Level Indicator Assembly | 1.00 | set | | |
| b.1a. | <i>Furnishing & Installation of Water Level Indicator and all its accessories in accordance with the approved plan.</i> | | | | |



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **REHABILITATION OF 1,500 CUBIC METER CYLINDRICAL GROUND STEEL TANK**
 Location: **SM VILLAGE, BRGY. SINAWAL, GENERAL SANTOS CITY**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

| ITEM NO. | DESCRIPTION | QUANTITY | UNIT | UNIT COST | AMOUNT |
|---------------------------|--|----------|-------|-----------|--------|
| C | ELECTRICAL WORKS | | | | |
| c.1 | Lighting Fixtures | 8.00 | sets | | |
| c.1a. | <i>Furnishing & Installation of 100watts LED Street light and its accessories.</i> | | | | |
| D | PAINTING WORKS | | | | |
| D.1 | Concrete & Steel Painting | 1,024.90 | sq.m. | | |
| d.1a. | <i>Painting of Exterior (Epoxy Paint)</i> | | | | |
| E | SPECIAL ITEMS | | | | |
| E.1 | Leak Testing | 1,500.00 | cu.m. | | |
| E.2 | Occupation Safety and Health Program | 1.00 | lot | | |
| E.3 | Mobilization and Demobilization | 1.00 | lot | | |
| TOTAL PROJECT COST | | | | | |

Submitted by: _____

Date: _____

Name of Bidder's representative: _____

Position: _____

Name of Bidder: _____