



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
General Santos City

EXPLORATORY / DRILLING OF PRODUCTION WELL
LEYSON COMPOUND, BRGY. CONEL, GSC

BILL OF QUANTITIES

	Description	Qty.	Unit	Unit Cost	Amount
F.	INSTALLATION OF CASINGS AND SCREENS INCLUDING STICK-UP PIPE	201	l.m.		
G.	FURNISHING AND INSTALLATION OF CASING CENTRALIZER	6	pc.		
H.	FURNISHING AND INSTALLATION OF GRAVEL PACK AND GRAVEL FILL PIPE	1	lot		
I.	TREATMENT WITH POLYPHOSPHATE SOLUTION	1	lot		
J.	WELL DEVELOPMENT				
J.1	Well Development (Jetting / Backwashing)	12	hour		
J.2	Well Development (Airlift Method)	12	hour		
J.3	Well Development (Surging/Brushing)	12	hour		
K.	STEP DRAWDOWN TEST, Max. Q = 70lps	1	lot		
L.	CONTINUOUS CONSTANT DISCHARGE RATE PUMPING TEST, Q = 70lps	72	hour		
M.	CEMENT GROUTING OF ANNULUS GROUND (25 m. DEPTH)	25	l.m.		
N.	FURNISHING AND INSTALLATION OF WELL HEAD CAP AND SOUNDING TUBE	1	lot		
O.	WATER QUALITY TESTING				
O.1	Physical and Chemical analysis (13 Parameters of PNSDW)	1	sample		
O.2	Bacteriological Analysis	1	sample		
O.3	Pesticide Analysis	1	sample		
O.4	Heavy Metal Test	1	sample		



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
General Santos City

EXPLORATORY / DRILLING OF PRODUCTION WELL
LEYSON COMPOUND, BRGY. CONEL, GSC

BILL OF QUANTITIES

	Description	Qty.	Unit	Unit Cost	Amount
P.	WELL CAMERA AFTER WELL REHABILITATION	1	lot		
Q.	SPECIAL ITEMS				
Q.1	Provision of Field Office for Resident Engineer	1	lot		
Q.2	Project Signboard (GSCWD and COA)	2	set		
Q.3	Occupation Safety and Health Program	1	lot		
Q.4	Mobilization and Demobilization	1	lot		
	TOTAL ESTIMATED PROJECT COST				

Submitted by: _____

Name of representative of Bidder _____

Position _____

Name of Bidder _____