Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
E. Fernandez St. Lagao, General Santos City
Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
E-mail Address: gscwaterdistrict@yahoo.com

Project: **FABRICATION AND DELIVERY OF INVENTORY CABINET AND GI PIPE TRAY AT PS NO. 16 WAREHOUSE**
Location: **PS NO. 16 PUROK UDAGRE, BRGY. CONEL, GSC**
Owner: **GENERAL SANTOS CITY WATER DISTRICT**
Subject: **BILL OF QUANTITIES**

ITEM NO.		DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
A		**FABRICATION AND DELIVERY OF INVENTORY CABINET**				
1		**INVENTORY CABINETS (2NOS.)**	**1**	LOT		
	A.1	*Furnishing and Fabrication of 20mm Thick Marine Plywood - for all Horizontal Platforms*				
	A.2	*Furnishing and Fabrication 12mm Thick Marine Plywood - for all Sidings*				
	A.3	*Furnishing and Fabrication 50mm x 50mm x 5mm Thick Angle Bar - for Steel Framings*				
	A.4	*Furnishing and Fabrication 38mm x 4.5mm Thick Flat Bar - for Steel Framings*				
	A.5	*Furnishing and Fabrication 38mm x 3.0mm Thick Flat Bar - for Steel Framings*				
	A.6	*Furnishing and Installation Stainless Steel Latch Bolt - for Door Locks*				
2		**GI PIPE TRAY**	**2**	NOS.		
	A.11	*Furnishing and Fabrication of 50mm x 50mm x 5mm Thick Angle Bar - for Steel Framings*				
	A.12	*Furnishing and Installation Heavy Duty Caster Wheel with Lock - 100mm*				
3		**PAINTING WORKS**	**1**	LOT		

Project: **FABRICATION AND DELIVERY OF INVENTORY CABINET AND GI PIPE TRAY AT PS NO. 16 WAREHOUSE**

Location: **PS NO. 16 PUROK UDAGRE, BRGY. CONEL, GSC**

Owner: **GENERAL SANTOS CITY WATER DISTRICT**

Subject: **BILL OF QUANTITIES**

ITEM NO.		DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	A.13	*Furnishing and Applying of Epoxy Paint Primer and Epoxy Enamel Paint*				
	Total Project Cost					

Note:

PLEASE REFER TO APPROVED PLAN FOR FURTHER DETAILS

Submitted by   : _____   Date: _____

Name of representative of Bidder : _____

Position: : _____

Name of Bidder   : _____