



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **PROPOSED CONSTRUCTION OF MATERIALS RECOVERY FACILITY AT PS NO. 16**
 Location: **PRK. UDAGRE, BGY. CONEL, GENERAL SANTOS CITY**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
A	EARTHWORKS				
A.1	Excavation of Column Footing	32.00	cu.m.		
A.2	Gravel 3/4" Bedding	9.00	cu.m.		
A.3	Backfilling and Compaction	11.00	cu.m.		
B	FORMWORKS				
B.1	Formworks Installation	18.00	sq.m.		
a	<i>Furnishing and Installation of 1/2" thk. Plywood and Assorted Sizes of Coco Lumber</i>				
C.	REBARWORKS				
C.1	Rebarworks Fabrication and Installation	1,000.00	kgs.		
a	<i>Rebarworks Fabrication and Installation - 10mm dia. and 12mm dia. for Footing, Pedestal, Column main bars and stirrups</i>				
D	CONCRETE WORKS				
D.1	Concrete Works with Compressive Strength of 3000psi @28 days	23.00	cu.m.		
a	<i>Concreting of footing, slab on grade, and pedestal</i>				
E	MASONRY WORKS				
E.1	Concrete Hollow Block Laying and Plastering	22.00	sq.m.		
a	<i>Furnishing and Installation 4" CHB Wall</i>				
F	STEEL FRAMING WORKS				
F.1	Steel Framing Installation	6,083.00	kgs.		
a	<i>Furnishing and Installation of 2" dia. GI Pipe Sch. 40</i>				
b	<i>Furnishing and Installation of 1" x 1" x 5mm Thickness Angle Bar</i>				
c	<i>Furnishing and Installation of 4mm Thickness Steel Matting</i>				
F.2	Steel Roof Truss				
a	<i>Furnishing and Installation of 50mm x 50mm x 5mm Angle Bar for Truss Top and Bottom Chord</i>				
b	<i>Furnishing and Installation of 38mm x 38mm x 5mm Angle Bar for Truss Web Members</i>				



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **PROPOSED CONSTRUCTION OF MATERIALS RECOVERY FACILITY AT PS NO. 16**
 Location: **PRK. UDAGRE, BGY. CONEL, GENERAL SANTOS CITY**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
c	Furnishing and Installation of 38mm x 75mm X 50mm X 1.2 C Purlins				
G	ROOFING WORKS				
G.1	Installation of Rib Type Roofing	162.00	sq.m.		
a	Furnishing and Installation of Rib-type Long Span Pre-painted Roofing, 0.40mm thk x 1.05m effective width				
b	Furnishing and Installation of Pre formed Pre-painted Ridge Roll 0.60mm thk.including all its accessories				
H	PAINTING WORKS				
H.1	Painting Works for Steel	1.00	lot		
a	Furnishing and Painting of Epoxy Paint for Steel				
I	ELECTRICAL WORKS				
H.1	Power and Lighting Works	1.00	lot		
a	Furnishing and Installation of Tube LED Lamp 36W w/ Receptacle				
b	Furnishing and Installation of 3.5mm and 8.0mm THHN Wire				
c	Furnishing and Installation of Circuit Breaker 15amp and 20amp				
d	Furnishing and Installation of 2 gang surface mounted switch				
e	Furnishing and Installation of 1 gang surface mounted switch				
	Total Project Cost				

Note:

PLEASE REFER TO APPROVED PLAN FOR FURTHER DETAILS

Submitted by : _____ Date: _____
 Name of representative of Bidder : _____
 Position: : _____
 Name of Bidder : _____