



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
E. Fernandez Street, Barangay Lagao General Santos
Telephone No.: 552-3824; Telefax No.: 553-4960
Email Address: gscwdprocurement@yahoo.com

GPM-014-2

REQUEST FOR QUOTATION

RFQ #: 3-0222-050 DATE: 02/22/2022

SUPPLIER: _____
ADDRESS: _____
TELEPHONE NO. : _____
TIN NO. : _____

Dear Sir/Madam,

Pls. quote your lowest price on the item/s listed below subject to general condition stating the shortest time of delivery and submit your quotation duly signed by your representative not later than 02/28/2022, Pls. furnish this office the following articles subject to the terms and conditions contained therein.

ITEM NO.	DESCRIPTION	QTY.	UNIT	UNIT PRICE
1	CONSTRUCTION/LABOR AND MATERIALS : PLEASE SEE ATTACHED SCOPE OF WORK-ABC: PHP 248,050.08 ##### nothing follows #####	1	LOT	P

Date of Delivery: _____
Price Validity : _____
Terms of Payment: _____

Place of Delivery: GSCWD Bodega
*****No partial delivery allowed****
Note: 6% WITHHOLDING TAX DEDUCTION
PR NO.: 0222-045

Requested by:

ANDREW H. NADAL JR.
Administration Services Assistant A

Price quoted by:

Supplier

Date



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
E. Fernandez St., Lagao, General Santos City

Project : **RENOVATION OF PERIMETER FENCE**
Location : **PUMPING STATION NO.7, PHILBANKING VILLAGE, BRGY. APOPONG, GSC**
Owner : **GENERAL SANTOS CITY WATER DISTRICT**

SCOPE OF WORK

PART 1. GENERAL

1.1. SCOPE

1. Provide all labor, equipments and materials needed in demolition/removal, concrete/masonry, steel, electrical/lighting and painting works for renovation of existing perimeter fence.
2. Works includes but not limited to mobilization, earthworks, concrete, masonry, steel, painting, demobilization and other works specified in the approved plan.

PART 2. EXECUTION

2.1. GENERAL

1. The contractor shall make his own inspection and assessment of the existing perimeter fence prior to the demolition and renovation. The site will be prepared in accordance with the approved plans.
2. All works are subject for the inspection and approval of the Assigned Engineer.
3. All necessary labor and materials needed for the completion of the project shall be shouldered by the contractor.
4. The contractor shall pay liquidated damages if failed to complete within the agreed time.

2.2 WORKS

2.2.1 DEMOLITION/REMOVAL

The Contractor shall perform all demolition/removal works including labor, materials and equipments.

2.2.2 EARTHWORKS

- a. Excavation shall include the removal of materials of whatever nature encountered that will interfere with the proper execution and completion of work. It shall be carried to the grade of the bottom of the footing or the slab or as indicated in the drawing.
- b. Soil excavated shall be placed as backfill and shall be compacted.

2.2.3 CONCRETE WORKS

- a. Cement shall be Portland and one brand. Aggregates shall be well graded, clean, hard particles of gravel or crushed rock.
- b. All reinforcing steel bars used shall be deformed type, new, free from rust and defects.

2.2.4 STEEL WORKS

- a. The contractor shall furnish, fabricate and install metal works as specified herein and shown in approved plans.
- b. All materials to be provided and used shall be new, unused, conformed to the Standard Specification for Structural Steel.
- c. The contractor shall accomplish the work in complete and finished manner and insure the highest quality of workmanship in accordance with the approved plan.

2.2.5 ELECTRICAL/LIGHTING

- a. The contractor shall furnish 200 watts outdoor/weatherproof LED lights (solar street lights) with solar panels and brackets (as specified herein and shown in approved plans).
- b. All lightings shall be new, unused, conformed to the DTI and other Electrical Standard.

2.2.6 PAINTING WORKS

- a. Metal surfaces shall be clean, dry and free from mill scale, rust, grease oil, or any substance that could affect the quality of painting.
- b. All surfaces shall be painted, coated with proper consistency, brushed/rolled evenly and free of brush marks.
- c. No painting shall be done under conditions of weather, moisture or temperature unsuited to good work nor until previous coat is hard and dry.

2.2.7 FORMWORKS

- a. All formworks/scaffolds shall be provided by the contractor.

2.3 DISPOSAL AND RESTORATION

At the completion, all excess materials, debris and rubbish shall be disposed properly at the expense of the contractor.

Prepared by:


LOREVIN V. EVANGELIO, RMEE
Engineering Asst. B

Checked by:


DLUANIE R. ENERIO, RMEE
Principal Engineer C, Production

Reviewed by:


ROGELIO A. BESANA JR., CE, RMP
Asst. General Manager A
Operations and Technical Services

Approved by:


ARN B. GELLANGARIN, PME
General Manager A



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
E. Fernandez St. Lagao, General Santos City
Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
E-mail Address: gscwaterdistrict@yahoo.com
www.gensanwater.gov.ph

PROJECT DESCRIPTION

Project Name : PROPOSED RENOVATION OF PERIMETER FENCE

Location : PS# 7, PHI BANKING VILLAGE, BRGY. FATIMA, GSC

Undertaken by : BY CONTRACT

Estimated Amount : PHP 248,050.08

Charge to : LAND IMPROVEMENT

Date Started : UPON APPROVAL

Project Duration : 17 Calendar Days

Received by: *[Signature]*
11/16/17