



Republic of the Philippines

GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St., Brgy. Lagao, General Santos City

Telephone No.: 552-3824; Telefax No.: 553-4960

Email Address: gscwaterdistrict@yahoo.com

Project: **CONSTRUCTION OF GENSET SHED**
 Location: **LOT 764-A-1 NUPOL, CONEL, GSC**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

| ITEM NO. | DESCRIPTION | QUANTITY | UNIT | UNIT COST | AMOUNT |
|------------|---|----------|-------|-----------|--------|
| A. | MOBILIZATION | 1.00 | l.s. | | - |
| B. | GENSET SHED | | | | |
| B.1 | EARTHWORKS | | | | |
| a. | EARTH EXCAVATION | 11.00 | cu.m. | | |
| b. | GRAVEL BEDDING | 6.00 | cu.m. | | - |
| c. | BACKFILLING AND COMPACTION | 17.00 | cu.m. | | - |
| B.2 | CONCRETE WORKS | | | | |
| a. | STRUCTURAL CONCRETE (Class A) Concrete Works with Compressive strength of 3000psi @ 28 days | 12.00 | cu.m. | | |
| b. | REINFORCING STEEL (DEFORMED) | 452.00 | kgs | | - |
| c. | FORMWORKS & SCAFFOLDING | 1.00 | l.s. | | - |
| B.3 | MASONRY WORKS | | | | |
| a. | MASONRY WORKS (CONCRETE HOLLOW BLOCKS) | 26.00 | sq.m. | | - |
| B.4 | FINISHING WORKS | | | | |
| a. | CEMENT PLASTER FINISH | 11.00 | sq.m. | | - |
| B.5 | ROOF FRAMING, ROOFING WORKS AND STEEL WORKS | | | | |
| a. | ROOFING WORKS Furnishing and Installation of Rib-Type Long Span Pre-painted Roofing, 0.40mm thk x 1.05 effective width, including cee purlins and other accessories. | 57.00 | l.m. | | |
| b. | STRUCTURAL STEEL (TRUSSES) | 305.00 | kgs | | - |
| c. | STRUCTURAL STEEL (PURLINS) | 164.00 | kgs | | - |
| d. | ROOFING ACCESSORY (RIDGE ROLLS, 0.60mm thk) | 10.00 | l.m. | | - |
| e. | METAL STRUCTURE ACCESSORIES (BUILT-UP GIRT) | 198.00 | kgs | | - |
| f. | METAL STRUCTURE ACCESSORIES (G.I. PIPE COLUMN) | 3.00 | len | | - |
| g. | METAL STRUCTURE ACCESSORIES (STEEL PLATE SUPPORT, GUSSET) | 80.00 | kgs | | - |
| h. | HARDWARE (ANCHOR BOLT, NUT & WASHER) | 24.00 | ea | | - |

| | | | | | |
|------------|--|-------|-------|--|---|
| B.6 | ELECTRICAL WORKS | | | | |
| a. | Furnishing and Installation of lighting outlet, 25 watts led lamp including its switches, wires and other accessories. | 1.00 | l.s. | | - |
| b. | Other miscellaneous items to complete the installation of electrical works | 1.00 | l.s. | | - |
| B.7 | PAINTING WORKS | | | | |
| a. | PAINTING WORKS | 38.00 | sq.m. | | - |
| C. | DEMOBILIZATION | 1.00 | l.s. | | - |
| | TOTAL PROJECT COST | | | | - |

NOTE:

PLEASE REFER TO SPECIFICATION FOR FURTHER DETAILS

Submitted by

Date: _____

Name of representative of Bic: _____

Position: _____

Name of Bidder: _____

Issued on :