



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
 E. Fernandez Street, Barangay Lagao General Santos
 Telephone No.: 552-3824; Telefax No.: 553-4960
 Email Address: gscwdprocurement@yahoo.com

GPM-014-4

REQUEST FOR QUOTATION

RFQ #: 3-0224-046 DATE: 2/12/2024

SUPPLIER: _____
 ADDRESS: _____
 TELEPHONE NO. : _____
 TIN NO. : _____

Dear Sir/Madam,

Pls. quote your lowest price on the item/s listed below subject to general condition stating the shortest time of delivery and submit your quotation duly signed by your representative not later than 2/16/2024, Pls. furnish this office the following articles subject to the terms and conditions contained therein.

Instructions :

1. Accomplish this Request for Quotation duly, correctly, and completely.
2. Do not alter the contents of this form in any way.
3. If Technical Specifications/ Terms of Reference is provided, prospect bidder (supplier /service provider) must indicate and signify compliance to every parameter in the specification.

ITEM NO.	DESCRIPTION	QTY.	UNIT	UNIT PRICE
1	CONSTRUCTION/LABOR AND MATERIALS : SEE ATTACHED APPROVED PLAN-ABC: PHP 376,734.32 ##### nothing follows #####	1	LOT	P

Date of Delivery: _____
 Price Validity : _____
 Mode of Payment: _____

Place of Delivery: GSCWD Bodega
 *****No partial delivery allowed*****
 Note: 6% WITHHOLDING TAX DEDUCTION
 PR NO.: 0124-152

Requested by:

GESEM R. CABAÑERO
 Supervising Material
 Planning Officer

Price quoted by:

 Supplier

 Date



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
E. Fernandez St., Brgy. Lagao, General Santos City
Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
www.gensanwater.gov.ph



SCOPE OF WORK

Project Title: **Proposed Construction of Comfort Rooms**
Location: **PS No.24, Zone XI-B, Brgy. Fatima, PS No.25, Purok 6, Brgy. Conel
& PS No.26 SM Village, Brgy. Sinawal**

1. The winning bidder shall provide/supply all necessary materials, labor and equipment and other necessary items to complete the construction of the said project.
2. All works shall be performed by the winning bidder in accordance with the approved plan and specifications of the owner as enumerated below.

1. EARTHWORKS

- a. *Earth Excavation*
- b. *Gravel Beddings*
- c. *Backfilling and Compaction*

2. CONCRETE and MASONRY WORKS

- a. Formworks
- b. Concrete (Walls should be smooth finished)
- c. Furnishing and Installation of 4"CHB including reinforcement and concrete decorative louver blocks
- d. Tiled flooring (30cmx30cm)

4. Fabricated Materials

- a. DOOR, PVC
 - Furnishing and installation of PVC toilet door with louver set plain and complete hardware accessories

5. CEILING AND ROOFING WORKS

a. ROOFING WORKS

- Furnishing and Installation of rib-type long span pre-painted Roofing, 2.50m x 0.40mm thk x 1.05 effective width, including cee purlins 75mmx 50mmx1.2mm and other accessories.

b. CEILING WORKS

- Furnishing and installation of ceiling, 4'x8'x3.5mm thk. Fiber cement board, paint finished including its metal furring ceiling frames, trusses, etc. See approved plan.

6. PLUMBING WORKS

- a. Furnishing and installation of toilet bowl, sanitary pipes and fittings
- b. Water supply pipes and fixtures
- c. Sewer lines

8. ELECTRICAL/LIGHTINGS

A. LIGHTING FIXTURES AND LAMPS

- Furnishing and Installation of electrical wires (3.5mm² THHN), lamps, switch, lighting fixtures and accessories.

9. PAINTING WORKS

a. PAINTING WORKS

- Inside and ceiling (white) and outside (blue)
- Trusses/frames (red oxide primer)

10. SEPTIC VAULT


- Furnishing and Installation of 4" CHB including reinforcement
- *Floor concrete with three (3) chambers with manholes*
- *See approved plans*

- 3. All waste materials shall be cleared and properly disposed by the contractor.
- 4. The project duration is thirty (30) calendar days and shall commence three (3) days after the receipt of Notice to Proceed.
- 5. Authorized representative of General Santos City Water District shall be assigned to monitor/inspect the implementation of the project.
- 6. One (1) year warranty under normal condition shall be provided by the contractor.
- 7. The progress payment shall be made upon reaching 30% and 100% project completion.

Prepared by:


ENGR. LOREVIN V. EVANGELIO
WUDO-A

Checked by:


ENGR. EDMUND L. BADAL
Principal Engineer C, WQPEMD

Approved by:


ENGR. ROGELIO A. BESANA JR., RMP
Asst. General Manager for Operations & Technical Services