



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
E. Fernandez Street, Barangay Lagao General Santos
Telephone No.: 552-3824; Telefax No.: 553-4960
Email Address: gscwdprocurement@yahoo.com

GPM-014-3

REQUEST FOR QUOTATION

RFQ #: 3-0323-023 DATE: 03/09/2023

SUPPLIER: _____
ADDRESS: _____
TELEPHONE NO. : _____
TIN NO. : _____

Dear Sir/Madam,

Pls. quote your lowest price on the item/s listed below subject to general condition stating the shortest time of delivery and submit your quotation duly signed by your representative not later than 03/15/2023, Pls. furnish this office the following articles subject to the terms and conditions contained therein.

ITEM NO.	DESCRIPTION	QTY.	UNIT	UNIT PRICE
1	CONSTRUCTION/LABOR AND MATERIALS : PLEASE SEE ATTACHED SCOPE OF WORK-ABC: PHP 70,100.00 ##### nothing follows #####	1	LOT	P

Delivery term: _____
Price Validity : _____
Terms of Payment: _____

Place of Delivery: GSCWD Bodega
*****No partial delivery allowed****
Note: 6% WITHHOLDING TAX DEDUCTION
PR NO.: 0323-021

Requested by:

GESEM R. CABAÑERO
MATERIAL PROCUREMENT
OFFICER A

Price quoted by:

Supplier

Date



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **REHABILITATION OF RESIDENTIAL FACILITY (BAHAY PAG ASA) AT BGY. SINAWAL GSC**
 Location: **BGY. SINAWAL, GENERAL SANTOS CITY**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
A	DEMOLITION & CONCRETE RESTORATION WORKS	1	LOT		
A.1	Demolition of concrete to expose existing embedded sanitary pipes				
A.2	Removal of existing sanitary pipes				
A.3	Furnishing and pouring of concrete mixture - Portland Cement, Sand S1 and Gravel 3/4				
B	SOIL AND WASTE PIPE NEW INSTALLATION @ TOILET & SHOWER AREA	36	LM		
B.1	Furnishing and Installation of 3" Sanitary PVC pipes and fittings for new soil pipe connection				
B.2	Furnishing and Installation of 2" Sanitary PVC pipes and fittings for new soil pipe connection				
B.3	Furnishing and Installation of 3" Stainless Steel floor drain with strainer for new soil pipe connection				
B.4	Furnishing and Installation of 2" Stainless Steel floor drain with strainer for new soil pipe connection				
C	WALL PARTITIONS AND DOORS @ TOILET & SHOWER AREA	10	SQM.		
C.1	Furnishing and Installation of 100mm Concrete Hollow Block wall for shower and toilet partitions				
C.2	Furnishing and Installation of Deformed Bars 10mm dia. - 6m for shower and toilet partitions reinforcements				
C.3	Furnishing and Installation of 40mm PVC Door 650mm x 1500mm for shower and toilet doors				
	Total Project Cost				

Note:

PLEASE REFER TO APPROVED PLAN FOR FURTHER DETAILS

Submitted by _____ :

Date: _____

Name of representative of Bidder _____ :

Position: _____ :

Name of Bidder _____ :