



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
E. Fernandez Street, Barangay Lagao General Santos
Telephone No.: 552-3824; Telefax No.: 553-4960
Email Address: gscwdprocurement@yahoo.com

GPM-014-3

REQUEST FOR QUOTATION

RFQ #: 3-0323-024 DATE: 03/09/2023

SUPPLIER: _____
ADDRESS: _____
TELEPHONE NO. : _____
TIN NO. : _____


Dear Sir/Madam,

Pls. quote your lowest price on the item/s listed below subject to general condition stating the shortest time of delivery and submit your quotation duly signed by your representative not later than 03/15/2023, Pls. furnish this office the following articles subject to the terms and conditions contained therein.

ITEM NO.	DESCRIPTION	QTY.	UNIT	UNIT PRICE
1	CONSTRUCTION/LABOR AND MATERIALS : PLEASE SEE ATTACHED SCOPE OF WORK-ABC: PHP 286,600.00 ##### nothing follows #####	1	LOT	P

Delivery term: _____
Price Validity : _____
Terms of Payment: _____

Place of Delivery: GSCWD Bodega
*****No partial delivery allowed****
Note: 6% WITHHOLDING TAX DEDUCTION
PR NO.: 0323-022

Requested by:

GESEM R. CADAÑERO
MATERIAL PROCUREMENT
OFFICER A

Price quoted by:

Supplier

Date



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **CITY SOCIAL WELFARE AND DEVELOPMENT OFFICE, GSC - IMPROVEMENTS OF FACILITIES**
 Location: **BGY. DADIANGAS EAST, GENERAL SANTOS CITY**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
A	DOOR REMOVAL AND REPLACEMENTS	15	SET		
	Door Replacement				
A.1	<i>Furnishing and Installation of D1 - 40mm thick hollow core molded door 900mm x 2150mm at GF Offices - 4 units</i>				
A.2	<i>Furnishing and Installation of D2 - 40mm thick PVC door 600mm x 1900mm at GF Toilet and Shower Room - 5 units</i>				
A.3	<i>Furnishing and Installation of D3 - 40mm thick hollow core molded door 800mm x 2150mm at GF and 2F Toilet Room - 2 units</i>				
A.4	<i>Furnishing and Installation of D4 - 40mm thick hollow core molded door 900mm x 2100mm at GF Toilet and Breastfeeding Room - 2 units</i>				
A.5	<i>Furnishing and Installation of D5 - 40mm PVC door door 900mm x 1800mm at GF Breastfeeding Room - 1 unit</i>				
A.6	<i>Furnishing and Installation of D6 - 40mm PVC door door 600mm x 2100mm at GF Breastfeeding Room Toilet - 1 unit</i>				
A.7	<i>Furnishing and Installation of Stainless Steel 304 - Door Knob at Doors</i>				
A.8	<i>Furnishing and Installation of Stainless Steel 304 - Door Hinge 3" at Doors</i>				
A.9	<i>Furnishing and Installation of Door Handle and Brass Bolt at Doors</i>				
A.10	<i>Concrete Restorations on Door Jambs</i>				
B	ALUMINIUM AND GLASS DOORS AND WINDOW	3	SET		
B.1	<i>Furnishing and Installation of D7 - Aluminium and glass partition with 1no. Sliding door and Hardiflex partition at bottom (see dimensions) at 2F Office area in front of staircase</i>				
B.2	<i>Furnishing and Installation of D8 - Aluminium and glass partition with 1no. Sliding door and Hardiflex partition at bottom (see dimensions) at 2F Office area</i>				



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **CITY SOCIAL WELFARE AND DEVELOPMENT OFFICE, GSC - IMPROVEMENTS OF FACILITIES**
 Location: **BGY. DADIANGAS EAST, GENERAL SANTOS CITY**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
B.3	<i>Furnishing and Installation of Aluminium framed sliding window - 6mm tinted glass at storage area</i>				
C	DRY WALL PARTITION	12	SQ.M.		
C.1	<i>Furnishing and Installation of Double Metal Furring 19mm x 50mm x 0.60mm Thickness - 5m Length at wall partition framings</i>				
C.2	<i>Furnishing and Installation of 1/4" Thickness Ordinary Plywood at inner layer of wall partition</i>				
C.3	<i>Furnishing and Installation of 3/16" Thickness Hardiflex at outer layer of wall partition</i>				
C.4	<i>Furnishing and Installation of 2" Mesh Tape at wall joints</i>				
C.5	<i>Furnishing and Application Skimcoat at wall partitions</i>				
C.6	<i>Furnishing and Application of Acrylic Semi Gloss Paint at walls</i>				
D	WINDOW BLINDS & BENCH	5	SET		
C.1	<i>Furnishing and Installation of B1 - 3800mm x 1200mm - Window Blinds Semi Blackout - Design and Color to be decided by the owner at 2F Office area</i>				
C.2	<i>Furnishing and Installation of B2 - 3300mm x 1200mm - Window Blinds Semi Blackout - Design and Color to be decided by the owner at 2F Office area</i>				
C.3	<i>Furnishing and Installation of B3 - 3800mm x 1200mm - Window Blinds Semi Blackout - Design and Color to be decided by the owner at 2F Office area</i>				



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **CITY SOCIAL WELFARE AND DEVELOPMENT OFFICE, GSC - IMPROVEMENTS OF FACILITIES**
 Location: **BGY. DADIANGAS EAST, GENERAL SANTOS CITY**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
C.4	<i>Furnishing and Installation of 1" x 2" S4S Wood - 12ft. and 2" x 2" S4S Wood - 12ft. For wooden bench</i>				
C.5	<i>Furnishing and Application of Acrylic Primer Paint - White</i>				
C.6	<i>Furnishing and Application of Acrylic Paint - White</i>				
E	PAINTING WORKS - CONFERENCE AND OFFICE ROOM	100	SQ.M.		
C.1	<i>Furnishing and Application of Acrylic Primer Paint</i>				
C.2	<i>Furnishing and Application of Acrylic Semi Gloss Paint - White for walls</i>				
C.3	<i>Furnishing and Application of Acrylic Semi Gloss Paint - White for Ceiling</i>				
C.4	<i>Furnishing and Application of Tinting Colors - for Brown/Beige color of Ceiling Cornice and Walls</i>				
C.5	<i>Furnishing and Application of Patching Compound for wall imperfections repair</i>				
Total Project Cost					

Note:

PLEASE REFER TO APPROVED PLAN FOR FURTHER DETAILS

Submitted by _____ : _____ Date: _____

Name of representative of Bidder _____ : _____

Position: _____ : _____

Name of Bidder _____ : _____