



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
 E. Fernandez Street, Barangay Lagao General Santos
 Telephone No.: 552-3824; Telefax No.: 553-4960
 Email Address: gscwdprocurement@yahoo.com

GPM-014-2

REQUEST FOR QUOTATION

RFQ #: 3-0623-016 DATE: 6/8/2023

SUPPLIER: _____
 ADDRESS: _____
 TELEPHONE NO. : _____
 TIN NO. : _____

Dear Sir/Madam,

Pls. quote your lowest price on the item/s listed below subject to general condition stating the shortest time of delivery and submit your quotation duly signed by your representative not later than 6/14/2023, Pls. furnish this office the following articles subject to the terms and conditions contained therein.

ITEM NO.	DESCRIPTION	QTY.	UNIT	UNIT PRICE
1	REPAIR (LABOR & MATERIALS) : SEE ATTACHED PLAN.-ABC: PHP 100,900.00 ##### nothing follows #####	1	LOT	P

Delivery Term: _____
 Price Validity : _____
 Terms of Payment: _____

Place of Delivery: GSCWD Bodega
 *****No partial delivery allowed*****
 Note: 6% WITHHOLDING TAX DEDUCTION
 PR NO.: 0523-086

Requested by:

GELEN R. CASABERO
 MATERIAL PROCUREMENT
 OFFICER A

Price quoted by:

 Supplier

 Date



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
E. Fernandez St., Brgy. Lagao, General Santos City
Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
www.gensanwater.gov.ph



SCOPE OF WORK

Project Title: **Repair and Repainting of Pump House, Genset Shed and CR at PS No.7.**

Location: **Philbanking, Apopong, General Santos City**

1. The winning bidder shall provide/supply all necessary materials, labor and equipment and other necessary items to complete the said project.
2. All works shall be performed by the winning bidder in accordance with the approved plan and specifications of the owner as enumerated below.

A PUMPHOUSE CEILING WORKS

A.1 REMOVAL OF EXISTING CEILING FRAMES & CEILING BOARDS

A.2 PUMPHOUSE CEILING WORKS INSTALLATION - INTERIOR & EXTERIOR

A.2.1 *Furnishing and Installation of Double Metal Furring 19mm x 50mm x 0.60mm Thickness x 5m Length*

A.2.2 *Furnishing and Installation of Carrying Channel 12mm x 38mm x 0.80mm Thickness x 5m Length*

A.2.3 *Furnishing and Installation of 3/16" Thickness Hardiflex for ceiling boards*

B PUMPHOUSE PAINTING

B.1 PUMPHOUSE PAINTING – FLOOR, WALL & DISCHARGE LINES

B.1.1 *Furnishing and Application of Wall Paint – Light Grey (Interior) and Azure Blue (Exterior).*

B.1.2 *Furnishing and Application of Floor Paint - Acrylic Paint (Light grey)*

B.1.3 *Furnishing and Application of Discharge lines - Epoxy Enamel Paint (ultramarine blue)*

B.2 PUMPHOUSE PAINTING - CEILING

B.2.1 *Furnishing and Application of Skimcoat - on ceiling boards*

B.2.2 *Furnishing and Application of Patching Compound - on ceiling boards*

B.2.3 *Furnishing and Application of Ceiling Paint Flat White Finish - on ceiling boards*

B.2.4 *Furnishing and Application of 2" Mesh Tape - on ceiling boards*

B.3 PUMPHOUSE PAINTING - ROOFING

B.3.1 *Furnishing and Application of Roofguard Paint*

B.3.2 *Furnishing and Application of Elastomeric Sealant - 0.50L for holes at roofing*

B.4 PUMPHOUSE PAINTING - LOGO & SIGNAGES

B.4.1 *Furnishing and Application Assorted Tinting Colors, Water & Oil Based - for logo and signages*

B.4.2 *Furnishing and Application Acrylic Paint - White - for logo and signages*

C PUMPHOUSE CONCRETE RESTORATIONS AND DOOR REPLACEMENT

C.1 EXHAUST FAN CONCRETE FINISH RESTORATION

C.1.1 *Furnishing and Restoration of Exhaust Fan Concrete Finish - Outer Edge*

C.2 REMOVAL OF EXISTING DOORS

C.3 INSTALLATION OF 900MM x 2150MM MOLDED DOOR

C.3.1 *Furnishing and Installation of 40mm thick hollow core molded door 900mm x 2150mm - for front door*

C.3.2 *Furnishing and Installation of Stainless Steel 304 - Door Knob*

C.3.3 *Furnishing and Installation of Stainless Steel 304 - Door Hinge 3"*

C.4 FABRICATION & INSTALLATION OF 900MM x 2150MM MARINE PLYWOOD DOOR

C.4.1 *Furnishing and Installation of Wooden Door Jamb - 1000mm x 2150mm - for rear door*

C.4.2 *Furnishing and Installation of 1 1/2" x 1 1/2" x 6' S4S Wood - for door frame of rear door*

C.4.3 *Furnishing and Installation of 1/4" Marine Plywood - for door panel of rear door*

C.4.4 *Furnishing and Installation of Acrylic Paint - for door finish*

C.4.5 *Furnishing and Installation of Stainless Steel 304 - Door Knob*

C.4.6 *Furnishing and Installation of Stainless Steel 304 - Door Hinge 3"*

D GENSET SHED PAINTING

D.1 STEEL FRAME, TRUSS, PURLINS & STEEL MATTING PAINTING

D.1.1 *Furnishing and Application of Rust Converter - on all steel frames*

D.1.2 *Furnishing and Application of Body Filler with Hardener - on all steel frames*

D.1.3 *Furnishing and Application of Epoxy Enamel Paint - on all steel frames*

D.2 ROOFING PAINT

D.2.1 *Furnishing and Application of Elastomeric Sealant - 0.50L for holes at roofing*

D.2.2 *Furnishing and Application of Roofguard Paint - for roofing paint*

E COMFORT ROOM CEILING REPAIR

E.1 REMOVAL OF EXISTING CEILING BOARDS AND FRAMES

E.2 CR FASCIA AND CEILING REPAIR

E.2.1 *Furnishing and Installation of 1/2" Thickness Hardiflex - for Fascia*

E.2.2 *Furnishing and Installation of 3/16" Thickness Hardiflex for ceiling boards*

E.2.3 *Furnishing and Installation of Double Metal Furring 19mm x 50mm x 0.60mm Thickness - 5m Length for ceiling frame*

E.2 CR PAINTING - CEILING

E.2.1 *Furnishing and Application of Skimcoat - on ceiling board*

E.2.2 *Furnishing and Application of Patching Compound - on ceiling board*

3. All waste materials shall be cleared and properly disposed by the contractor.
4. The project duration is twenty one (21) calendar days and shall commence five (5) days after the receipt of Notice to Proceed.
5. Authorized representative of General Santos City Water District shall be assigned to monitor/inspect the implementation of the project as per approved plan. See attached approved plan.

6. One (1) year warranty under normal condition shall be provided by the contractor.
7. The progress payment shall be made upon reaching 30% and 100% project completion.

Prepared by:


ENGR. LOREVIN V. EVANGELIO
WUDO-A

Checked by:


ENGR. EDMUND L. BADAL
Acting Division Manager, WQPEMD

Approved by:


ENGR. CORNELIO T. TURIJA JR.
Acting AGM for Operations & Technical Services



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **REPAIR & REPAINTING OF PUMPHOUSE, GENSET SHED AND CR @ PS NO. 7**
 Location: **BGY. APOPONG, GENERAL SANTOS CITY**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
A	PUMPHOUSE CEILING WORKS	37	SQ.M.		
A.1	REMOVAL OF EXISTING CEILING FRAMES & CEILING BOARDS	37	SQ.M.		
A.2	PUMPHOUSE CEILING WORKS INSTALLATION - INTERIOR & EXTERIOR	37	SQ.M.		
A.2.1	<i>Furnishing and Installation of Double Metal Furring 19mm x 50mm x 0.60mm Thickness x 5m Length</i>				
A.2.2	<i>Furnishing and Installation of Carrying Channel 12mm x 38mm x 0.80mm Thickness x 5m Length</i>				
A.2.3	<i>Furnishing and Installation of 3/16" Thickness Hardiflex for ceiling boards</i>				
B	PUMPHOUSE PAINTING	259	SQ.M.		
B.1	PUMPHOUSE PAINTING - FLOOR & WALL	163	SQ.M.		
B.1.1	<i>Furnishing and Application of Wall Paint - Acrylic Light Grey - for Interior and Azure Blue on Exterior - 118sq.m.</i>				
B.1.2	<i>Furnishing and Application of Floor Paint - Acrylic Light Grey - 45sq.m.</i>				
B.1.3	<i>Furnishing and Application of Steel Pipe Paint - Epoxy Enamel Ultra Marine Blue</i>				
B.2	PUMPHOUSE PAINTING - CEILING	37	SQ.M.		
B.2.1	<i>Furnishing and Application of Skimcoat - on ceiling boards</i>				
B.2.2	<i>Furnishing and Application of Patching Compound - on ceiling boards</i>				
B.2.3	<i>Furnishing and Application of Ceiling Paint Flat White Finish - on ceiling boards</i>				
B.2.4	<i>Furnishing and Application of 2" Mesh Tape - on ceiling boards</i>				
B.3	PUMPHOUSE PAINTING - ROOFING	59	SQ.M.		
B.3.1	<i>Furnishing and Application of Roofguard Paint</i>				
B.3.2	<i>Furnishing and Application of Elastomeric Sealant - 0.50L for holes at roofing</i>				
B.4	PUMPHOUSE PAINTING - LOGO & SIGNAGES	1	LOT		
B.4.1	<i>Furnishing and Application Assorted Tinting Colors, Water & Oil Based - for logo and signages</i>				



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **REPAIR & REPAINTING OF PUMPHOUSE, GENSET SHED AND CR @ PS NO. 7**
 Location: **BGY. APOPONG, GENERAL SANTOS CITY**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
B.4.2	<i>Furnishing and Application Acrylic Paint - White - for logo and signages</i>				
C	PUMPHOUSE CONCRETE RESTORATIONS AND DOOR REPLACEMENT	2	NOS.		
C.1	EXHAUST FAN CONCRETE FINISH RESTORATION	1	LOT		
C.1.1	<i>Furnishing and Restoration of Exhaust Fan Concrete Finish - Outer Edge</i>				
C.2	REMOVAL OF EXISTING DOORS	2	NOS.		
C.3	INSTALLATION OF 900MM x 2150MM MOLDED DOOR	1	NOS.		
C.3.1	<i>Furnishing and Installation of 40mm thick hollow core molded door 900mm x 2150mm - for front door</i>				
C.3.2	<i>Furnishing and Installation of Stainless Steel 304 - Door Knob</i>				
C.3.3	<i>Furnishing and Installation of Stainless Steel 304 - Door Hinge 3"</i>				
C.4	FABRICATION & INSTALLATION OF 900MM x 2150MM MARINE PLYWOOD DOOR	1	NOS.		
C.4.1	<i>Furnishing and Installation of Wooden Door Jamb - 1000mm x 2150mm - for rear door</i>				
C.4.2	<i>Furnishing and Installation of 1 1/2" x 1 1/2" x 6' S4S Wood - for door frame of rear door</i>				
C.4.3	<i>Furnishing and Installation of 1/4" Marine Plywood - for door panel of rear door</i>				
C.4.4	<i>Furnishing and Installation of Acrylic Paint - for door finish</i>				
C.4.5	<i>Furnishing and Installation of Stainless Steel 304 - Door Knob</i>				
C.4.6	<i>Furnishing and Installation of Stainless Steel 304 - Door Hinge 3"</i>				
D	GENSET SHED PAINTING	1	LOT		
D.1	STEEL FRAME, TRUSS, PURLINS & STEEL MATTING PAINTING	1	LOT		
D.1.1	<i>Furnishing and Application of Rust Converter - on all steel frames</i>				
D.1.2	<i>Furnishing and Application of Body Filler with Hardener - on all steel frames</i>				
D.1.3	<i>Furnishing and Application of Epoxy Enamel Paint - on all steel frames</i>				



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **REPAIR & REPAINTING OF PUMPHOUSE, GENSET SHED AND CR @ PS NO. 7**
 Location: **BGY. APOPONG, GENERAL SANTOS CITY**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
D.2	ROOFING PAINT	1	LOT		
D.2.1	<i>Furnishing and Application of Elastomeric Sealant - 0.50L for holes at roofing</i>				
D.2.2	<i>Furnishing and Application of Roofguard Paint - for roofing paint</i>				
E	COMFORT ROOM CEILING REPAIR	1	LOT		
E.1	REMOVAL OF EXISTING CEILING BOARDS AND FRAMES	1	LOT		
E.2	CR FASCIA AND CEILING REPAIR	1	LOT		
E.2.1	<i>Furnishing and Installation of 1/2" Thickness Hardiflex - for Fascia</i>				
E.2.2	<i>Furnishing and Installation of 3/16" Thickness Hardiflex for ceiling boards</i>				
E.2.3	<i>Furnishing and Installation of Double Metal Furring 19mm x 50mm x 0.60mm Thickness - 5m Length for ceiling frame</i>				
E.2	CR PAINTING - CEILING	1	LOT		
E.2.1	<i>Furnishing and Application of Skimcoat - on ceiling board</i>				
E.2.2	<i>Furnishing and Application of Patching Compound - on ceiling board</i>				
Total Project Cost					

Note:

PLEASE REFER TO APPROVED PLAN FOR FURTHER DETAILS

Submitted by _____ : _____ Date: _____

Name of representative of Bidder _____ : _____

Position: _____ : _____

Name of Bidder _____ : _____