



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
E. Fernandez Street, Barangay Lagao General Santos
Telephone No.: 552-3824; Telefax No.: 553-4960
Email Address: gscwdprocurement@yahoo.com

GPM-014-2

REQUEST FOR QUOTATION

RFQ #: 3-0623-066 DATE: 6/20/2023

SUPPLIER: _____
ADDRESS: _____
TELEPHONE NO. : _____
TIN NO. : _____

Dear Sir/Madam,

Pls. quote your lowest price on the item/s listed below subject to general condition stating the shortest time of delivery and submit your quotation duly signed by your representative not later than 6/24/2023, Pls. furnish this office the following articles subject to the terms and conditions contained therein.

ITEM NO.	DESCRIPTION	QTY.	UNIT	UNIT PRICE
1	REPAIR (LABOR & MATERIALS) : SEE THE ATTACHED PLAN.-ABC: PHP 120,900.00 ##### nothing follows #####	1	LOT	P

Date of Delivery: _____
Price Validity : _____
Terms of Payment: _____

Place of Delivery: GSCWD Bodega
****No partial delivery allowed****
Note: 6% WITHHOLDING TAX DEDUCTION
PR NO.: 0523-089

Requested by:

GESEM R. CABANERO
MATERIAL PROCUREMENT
OFFICER A

Price quoted by:

Supplier

Date



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
E. Fernandez St., Brgy. Lagao, General Santos City
Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
www.gensanwater.gov.ph



SCOPE OF WORK

Project Title: **Repair of Perimeter Fence and Sliding Gate at PS No. 22**

Location: **Purok Cabuay, Sinawal, General Santos City**

1. The winning bidder shall provide/supply all necessary materials, labor and equipment and other necessary items to complete the said project.
2. All works shall be performed by the winning bidder in accordance with the approved plan and specifications of the owner as enumerated below.

A.1 EARTHWORKS

A.1.1 *Excavation, Backfill & Compaction*

A.2 DEMOLITION OF STRUCTURALLY FAILED PERIMETER FENCE WALL

A.2.1 *Demolition, Clearing & Hauling of Debris*

A.3 REBARWORKS

A.3.1 *Furnishing & Installation of 10mm dia. Deformed Bars for CHB, Lintel Beam, Wall Footing, Stirrups & Ties*

A.3.2 *Furnishing & Installation of 12mm dia. Deformed Bars for Column main Bars & Footing Bed Bars*

A.3.3 *Furnishing & Application of Structural Anchor Epoxy*

A.4 FORMWORKS

A.4.1 *Furnishing & installation of 4' x 8' x 12mm thk. Plywood - False work*

A.4.2 *Furnishing & installation of 2" x 2" x 12' Coco lumber*

A.5 CONCRETE WORKS

A.5.1 *Furnishing & concreting with Portland Cement, Sand & Gravel*

A.6 MASONRY WORKS AND BARBWIRE REPAIR

A.6.1 *Furnishing & installation of 4" CHB Wall for Perimeter Fence*

A.6.2 *Furnishing & concreting with Portland Cement & Sand for CHB Mortar*

A.7 SLIDING STEEL GATE REPAIR

- A.7.1 *Furnishing & installation of 50 X 75 X 1.2mm B.I. Tubular for Repair and Replacement of Framings*
- A.7.2 *Furnishing & installation of G.A. 16 G.I. Plain Sheef for Repair and Replacement of Steel Sheets*
- A.7.3 *Furnishing & application of Epoxy Enamel Paint & Reducer*

A.8 STEEL GRILL DRAINAGE OUTLET

- A.8.1 *Furnishing & installation of 50 X 3mm Flat Bar for Framings*
- A.8.2 *Furnishing & installation of 16mm dia. Deformed Bars for Grills*

3. All waste materials shall be cleared and properly disposed by the contractor.
4. The project duration is twenty (20) calendar days and shall commence five (5) days after the receipt of Notice to Proceed.
5. Authorized representative of General Santos City Water District shall be assigned to monitor/inspect the implementation of the project as per approved plan. See attached approved plan.
6. One (1) year warranty under normal condition shall be provided by the contractor.
7. The progress payment shall be made upon reaching 30% and 100% project completion.

Prepared by:


ENGR. LOREVIN V. EVANGELIO
WUDO-A

Checked by:


ENGR. EDMUND L. BADAL
Acting Division Manager, WQPEMD

Approved by:


ENGR. CORNELIO T. TURIJA JR.
Acting AGM for Operations & Technical Services



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **CHB WALL PERIMETER FENCE AND SLIDING STEEL GATE REPAIR AT PS NO. 22 PUROK CABUAY, BGY. SINAWAL**
 Location: **PS NO. 22 PUROK CABUAY, BGY. SINAWAL, GSC**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
A.1	EARTHWORKS				
A.1.1	<i>Excavation, Backfill & Compaction</i>	9	Cu.M.		
A.2	DEMOLITION OF STRUCTURALLY FAILED PERIMETER FENCE WALL				
A.2.1	<i>Demolition, Clearing & Hauling of Debris</i>	4	Span		
A.3	REBARWORKS				
A.3.1	<i>Furnishing & Installation of 10mm dia. Deformed Bars for CHB, Lintel Beam, Wall Footing, Stirrups & Ties</i>	281	Kgs.		
A.3.2	<i>Furnishing & Installation of 12mm dia. Deformed Bars for Column main Bars & Footing Bed Bars</i>	183	Kgs.		
A.3.3	<i>Furnishing & Application of Structural Anchor Epoxy</i>	3	Tube		
A.4	FORMWORKS				
A.4.1	<i>Furnishing & installation of 4'x 8' x 12mm thk. Plywood - Falsework</i>	4	Nos.		
A.4.2	<i>Furnishing & installation of 2" x 2" x 12' Coco lumber</i>	8	Nos.		
A.5	CONCRETE WORKS				
A.5.1	<i>Furnishing & concreting with Protland Cement, Sand & Gravel</i>	3	Cu.M.		
A.6	MASONRY WORKS AND BARBWIRE REPAIR				
A.6.1	<i>Furnishing & installation of 4" CHB Wall for Perimeter Fence</i>	591	Nos.		
A.6.2	<i>Furnishing & concreting with Protland Cement & Sand for CHB Mortar</i>	59	Bags		



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **CHB WALL PERIMETER FENCE AND SLIDING STEEL GATE REPAIR AT PS NO. 22 PUROK CABUAY, BGY. SINAWAL**
 Location: **PS NO. 22 PUROK CABUAY, BGY. SINAWAL , GSC**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
A.7	SLIDING STEEL GATE REPAIR				
A.7.1	<i>Furnishing & installation of 50 X 75 X 1.2mm B.I. Tubular for Repair and Replacement of Framings</i>	3	Nos.		
A.7.2	<i>Furnishing & installation of G.A. 16 G.I. Plain Sheet for Repair and Replacement of Steel Sheets</i>	1	Sheet		
A.7.3	<i>Furnishing & application of Epoxy Enamel Paint & Reducer</i>	1	Lot		
A.8	STEEL GRILL DRAINAGE OUTLET				
A.8.1	<i>Furnishing & installation of 50 X 3mm Flat Bar for Framings</i>	8	Nos.		
A.8.2	<i>Furnishing & installation of 16mm dia. Deformed Bars for Grills</i>	21	Nos.		
	Total Project Cost				

Note:

PLEASE REFER TO APPROVED PLAN FOR FURTHER DETAILS

Submitted by _____ : _____ Date: _____

Name of representative of Bidder _____ : _____

Position: _____ : _____

Name of Bidder _____ : _____