



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
 E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **RENOVATION AND CONSTRUCTION FRONT PERIMETER FENCE AND GATE**
 Location: **PS NO. 7 PHILBANKING SUBDIVISION, BRGY. APOPONG, GSC**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
A.1	REMOVAL OF EXISTING CYCLONE WIRE FENCE AND GATE AND RAMP DEMOLITION				
A.1	Removal of Existing Cyclone Wire Fence and Gate	7	L.M.		
A.1	Demolition of Existing Ramp	1	Lot		
B.1	EXCAVATION				
B.1	Earth Excavation	3	CU.M.		
B.2	GRAVEL BEDDING				
B.2	GRAVEL BEDDING	2	CU.M.		
B.3	BACKFILLING				
B.3	BACKFILLING	2	CU.M.		
C.1	REBAR WORKS				
D.1	Rebarworks Fabrication and Installation	188	KGS.		
a	<i>Rebarworks Fabrication and Installation of 10mm dia. def bars for stirrups and ties, 12mm dia./16mm dia. def. bars for main bars.</i>	188	KGS.		
C.2	FALSEWORKS AND CONCRETE WORKS				
D.1	Concrete Works with Compressive Strength of 3000psi @28 days	2	CU.M.		
a	<i>Concreting of footing, column and beam</i>				
b	<i>Falseworks for Columns</i>				
D.1	MASONRY AND PLASTERING WORKS				
F.1	CHB Laying	24	SQ.M.		



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **RENOVATION AND CONSTRUCTION OF FRONT PERIMETER FENCE AND GATE**
 Location: **PS NO. 7 PHILBANKING SUBDIVISION, BRGY. APOPONG, GSC**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	a <i>Furnishing and Installation of 100mm thickness CHB with 10mm dia def. bar reinforcements</i>				
F.2	CHB Plastering	47	SQ.M.		
	a <i>Furnishing and Plastering of 12mm thickness concrete plaster (both sides on front and interior only on rear and side)</i>				
D.2	BARB WIRE				
G.1	Barb Wire Installation	29	L.M.		
	a <i>Furnishing and Installation of Galvanized Double Twist Barbed Wire - 50LM per roll</i>	1	ROLL		
	b <i>Furnishing and Installation of 25x 25 x 4mm angle bar support for barb wire</i>	2	NOS.		
D.3	SLIDING STEEL GATE FABRICATION AND INSTALLATION				
H.1	Sliding Steel Gate Fabrication and Installation	8	SQ.M.		
	<i>Furnishing and Installation of 50 x 75 x 1.2mm B.I. Tubular for gate framing</i>	3	NOS.		
	<i>Furnishing and Installation of 50 x 50 x 1.2mm B.I. Tubular for gate framing</i>	4	NOS.		
	<i>Furnishing and Installation of 50 x 50 x 6mm Angle Bar for Gate Runner</i>	2	NOS.		
	<i>Furnishing and Installation of GA 16 GI Plain Sheet for gate</i>	2	SHEETS		
	<i>Furnishing and Installation of 75 x 75 x 6mm Angle Bar for Top Roller Frame</i>	1	NOS.		
	<i>Furnishing and Installation of V-Shape Steel Gate Rollers for gate bottom guide</i>	6	NOS.		
	<i>Furnishing and Installation of Nylon Rollers for gate top guide</i>	4	NOS.		
D.4	PAINTING WORKS				



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **RENOVATION AND CONSTRUCTION FRONT PERIMETER FENCE AND GATE**
 Location: **PS NO. 7 PHILBANKING SUBDIVISION, BRGY. APOPONG, GSC**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
I.1	Paint for Steel Gate and Razor Wire Support	1	LOT		
a	<i>Furnishing and Painting of Epoxy Primer Gray for Gate and Razor Wire Support</i>	2	GAL.		
b	<i>Furnishing and Painting of Epoxy Enamel Paint for Gate and Razor Wire Support</i>	2	GAL.		
I.2	Paint for Perimeter Fence	1	LOT		
a	<i>Furnishing and Painting of Acrylic Latex Paint Primer for Perimeter Fence</i>	2	GAL.		
b	<i>Furnishing and Painting of Acrylic Semi Gloss Paint for Perimeter Fence</i>	2	GAL.		
E.1	SOLAR POWERED LIGHT POST INSTALLATION				
I.1	Solar Powered Light Post Installation	2	NOS.		



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **RENOVATION AND CONSTRUCTION FRONT PERIMETER FENCE AND GATE**
 Location: **PS NO. 7 PHILBANKING SUBDIVISION, BRGY. APOPONG, GSC**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	<i>Furnishing and Installation of 4" 200W Solar Street Light Outdoor LED Light Outlet Item no : S03-200W</i> <i>Solar panel : Polysilicon 6V/50W</i> <i>Battery : LiFePO4 3.2V 50AH/10pcs</i> <i>Chip source : SANAN2835, 406pcs CCT:6500-7000K Total lumen:3500LM</i> <i>Material : Aluminium+glass</i> <i>IP rating : IP65</i> <i>Charge time : 4-6H</i> <i>Working time : 12-15hrs, 1-2rainy days</i> <i>Lighting area : 200m²</i> <i>Control mode : time control and light control</i> <i>CTN/PCS : 1PCS/CTN</i> <i>Outer carton size : 48.5*15.5*68.5CM</i> <i>Lampbody size : 232*90*510mm</i> <i>Solar panel size : 444*17*670mm</i> <i>Outer carton size : 48.5*15.5*68.5CM</i> <i>Lampbody size : 232*90*510mm</i> <i>Solar panel size : 444*17*670mm</i>				
	Total Project Cost				

Note:

PLEASE REFER TO APPROVED PLAN FOR FURTHER DETAILS

Submitted by _____ : _____ Date: _____

Name of representative of Bidder _____ : _____

Position: _____ : _____

Name of Bidder _____ : _____