S CITY WATER BISTRICE.

Republic of the Philippines GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St., Brgy. Lagao, General Santos City Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960

www.gensanwater.gov.ph

SCOPE OF WORK

Project Title: Installation of Razor Wire and Solar Lights

Location: PS26, SM Village, Brgy. Sinawal

- 1. The winning bidder shall provide/supply all necessary materials, labor and equipment and other necessary items to complete the said project.
- 2. All works shall be performed by the winning bidder in accordance with the approved plan and specifications of the owner as enumerated below.

A. Razor Wire Installation

A.1 Furnishing and Installation of Razor Wire with steel support - (2 rows at bottom and 1 coil shaped at top)

B. PAINTING WORKS

- B.1 Furnishing and Application of Epoxy Primer Gray razor wire support
- B.2 Furnishing and Application of Epoxy Enamel Ultra Marine Blue Paint for Steel Sliding Gate

C SOLAR POWERED LIGHT POST INSTALLATION

Furnishing and Installation of 14 units 4" 200W Solar Street Light Outdoor

LED Light Outlet Item no : \$03-200W Solar panel : Polysilicon 6V/50W Battery : LiFePO4 3.2V 50AH/10pcs

Chip source: SANAN2835, 406pcs CCT:6500-7000K Total lumen:3500LM

Material: Aluminium+glass

IP rating : IP65 Charge time : 4-6H

Working time: 12-15hrs, 1-2rainy days

Lighting area: 200 m²

Control mode: time control and light control

C.1 CTN/PCS: 1PCS/CTN

Outer carton size: 48.5*15.5*68.5CM Lampbody size: 232*90*510mm Solar panel size: 444*17*670mm Outer carton size: 48.5*15.5*68.5CM Lampbody size: 232*90*510mm Solar panel size: 444*17*670mm

- 3. All waste materials shall be cleared and properly disposed by the contractor.
- 4. The project duration is ten (10) calendar days and shall commence three (3) days after the receipt of Notice to Proceed.
- 5. Authorized representative of General Santos City Water District shall be assigned to monitor/inspect the implementation of the project as per approved plan. See attached approved plan.
- 6. One (1) year warranty under normal condition shall be provided by the contractor.
- 7. The progress payment shall be made upon reaching 30% and 100% project completion.

Prepared by:

Checked by:

Acting Division Manager, WQPEMD

Approved by:

ENGR. ROGELIO A. BESANA JR., RMP

AGM for Operations & Technical Services