



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **ELEVATED WATER TANK REHABILITATION**
 Location: **SARANGANI HOMES PHASE 1, BRGY. SAN ISIDRO GSC**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
ELEVATED WATER TANK REHABILITATION					
SITE WORKS					
A.1	CLEARING AND GRUBBING	1	LOT		
EARTHWORKS					
B.1	EARTH EXCAVATION	1	CU.M.		
B.2	GRAVEL BEDDING	1	CU.M.		
CONCRETE WORKS - CONCRETE PAD					
C.1	REBAR WORKS	11	KGS.		
	<i>Furnishing & Installation of 12mm dia. Deformed Bars</i>				
C.2	CONCRETE WORKS	1	CU.M.		
	<i>Concrete works with 3000psi compressive strength @ 28 days</i>				
PIPELINES & PIPELINE APPURTENANCES					
D.1	DISCHARGE, DRAIN, SUPPLY, VENT AND OVERFLOW PIPES	120	LM		
	<i>Furnishing & Installation of 4" dia. X 20' G.I. Pipe Sched. 40</i>				
	<i>Furnishing & Installation of 4" dia. G.I. 90deg. Elbow</i>				
	<i>Furnishing & Installation of 4" dia. PVC Sanitary Pipe - 1000 Series</i>				
	<i>Furnishing & Installation of Stainless Steel BirdScreen</i>				
	<i>Furnishing & Application of PVC Solvent</i>				
D.2	FLOAT VALVES AND FLANGES	1	LOT		



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **ELEVATED WATER TANK REHABILITATION**
 Location: **SARANGANI HOMES PHASE 1, BRGY. SAN ISIDRO GSC**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	<i>Furnishing & Installation of 4" dia. Steel Flange</i>	2	SET		
	<i>Furnishing & Installation of 4" dia. Combi Flange</i>	2	SET		
	<i>Furnishing & Installation of Rubber Gasket</i>	1	KGS.		
	<i>Furnishing & Installation of 4" Float Valve with Brass Floater</i>	1	SET		
D.3	PIPE CLAMPS	1	LOT		
	<i>Furnishing & Installation of 500mm x 500mm x 8mm thk. Steel Plate</i>	22	KGS.		
	<i>Furnishing & Installation of 50mm x 8mm Flat Bar</i>	4	LENGTH		
	<i>Furnishing & Installation of 14mm dia. Bolt with Nut and Washer</i>	40	NOS.		
MISCELLANEOUS WORKS					
E.1	WATER LEVEL INDICATOR ASSEMBLY	1	LOT		
	<i>Furnishing & Installation of 10mm dia. Stainless Steel Rod</i>				
	<i>Furnishing & Installation of 3mm dia. Stainless Steel Rod</i>				
	<i>Furnishing & Installation of 75mm dia. Brass Pulley</i>				
	<i>Furnishing & Installation of 8mm Thick Plate Arrow Indicator</i>				
	<i>Furnishing & Installation of Assorted Reflectorized Stickers</i>				
	<i>Furnishing & Installation of Stainless Steel Floater with Fabricated Holder</i>				
	<i>Furnishing & Installation of 250mm x 50mm x 7m Tubular Aluminum</i>				
	<i>Furnishing & Installation of 50mm x 50mm x 3mm Thick Angle Bar</i>				
E.2	BARBED WIRE & GI PIPE FRAMES REPLACEMENT	27	LM		



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **ELEVATED WATER TANK REHABILITATION**
 Location: **SARANGANI HOMES PHASE 1, BRGY. SAN ISIDRO GSC**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	<i>Furnishing & Installation of Galvanized Double Twist Barbed Wire - 20LM per roll</i>				
	<i>Furnishing & Installation of 2" dia. X 20' G.I. Pipe Sched. 40</i>				
E.3	PAINTING WORKS	142	SQ.M.		
	Cleaning of Interior Shell of Water Tank using Steel Cup Brush - Assorted Sizes, Assorted Sand Paper & Scraper etc.				
	<i>Furnishing & Application of Rust Converter on Interior Shell of Water Tank</i>				
	<i>Furnishing & Application of Hydro Paint Primer</i>				
	<i>Furnishing & Application of Hydro Paint Finish</i>				
	<i>Furnishing & Application of Epoxy Primer Paint</i>				
	<i>Furnishing & Application of Epoxy Enamel Paint</i>				
	<i>Furnishing & Application of Masonry Wall Paint - Acrytex</i>				
	Total Project Cost				

Note:

PLEASE REFER TO APPROVED PLAN FOR FURTHER DETAILS

Submitted by : _____ Date: _____

Name of representative of Bidder : _____

Position: : _____

Name of Bidder : _____