



SCOPE OF WORK

Project Title: **Rehabilitation of 1,600 cu.m concrete reservoir**

Location: Purok Masunurin, San Isidro, General Santos City

1. The winning provider shall provide manpower, equipment, materials, tools, and other necessary equipment (scaffolds) for the said project such as the following works:

A. Repainting of 1,600 cu.m reservoir

A.1. Cleaning/scraping of uneven surfaces and dirt.

A.2. Painting of all portion of the said reservoir including stairs, railings, discharge lines, chamber, gratings, old booster house, etc.

A.3. Painting works are the following:

a. Concrete surfaces

- 1st and 2nd coat: Elastomeric paint: Light Gray Color

b. Steel

- **Discharge pipes** : 1st and 2nd coat: Epoxy Enamel Paint ultra- marine blue;
- **Steel Pipes and Air Vent**: Ultra-Marine Blue, Gloss
- **Steel Ladder**: 1st and 2nd coat: Epoxy Enamel Paint; Light Gray Color
- **Old booster house**: 1st and 2nd coat: Epoxy Enamel Paint; Light Gray Color
- **Discharge pipes & valves**: 1st and 2nd coat: Epoxy Enamel Paint ultra-marine blue;
- **Steel Grating**: 1st and 2nd coat: Epoxy Enamel Paint; Light Gray Color

A.4 Lettering of name and logo of reservoir (see attached plan)

A.5 Painting works shall be done during sunny weather only.

B. Installation of Steel Grating Chamber Cover (See attached approved plan.)

B.1 Furnishing of 2"x20'x6mm thk. Angle Bar

B.2 Furnishing of 2"x20'x6mm thk. Flat Bar

B.3 16mmØ Plain Round Bar

B.3 8mmØ Expansion Bolt

2. The winning bidder shall inform the assigned representative of GSCWD prior to start painting works.
3. All costs shall be shouldered by the winning bidder.
4. The project duration is 24 calendar days and shall commence five (5) days after the receipt of Notice to Proceed.
5. All works shall be observed by authorized representative of General Santos City Water District.
6. Painting works shall be done during sunny day only.
7. Warranty under normal condition shall be granted by service provider.
8. Accomplishment report and recommendations shall be submitted after work completion.
9. The progress payment shall be made upon 30% and 100% completion.

Prepared by:


Lorevin V. Evangelio, RMEE
WUDO-A

Checked by:


Edmund L. Badal, REE
Acting Div. Manager, WQPEMD

Approved by:


Rogelio A. Besana Jr., CE, RMP
Asst. Gen. Manager, Operations & Technical Services