



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT
E. Fernandez Street, Barangay Lagao General Santos
Telephone No.: 552-3824; Telefax No.: 553-4960
Email Address: gscwdprocurement@yahoo.com

GPM-014-4

REQUEST FOR QUOTATION

RFQ #: 3-1023-064 DATE: 10/24/2023

SUPPLIER: _____
ADDRESS: _____
TELEPHONE NO. : _____
TIN NO. : _____

Dear Sir/Madam,

Pls. quote your lowest price on the item/s listed below subject to general condition stating the shortest time of delivery and submit your quotation duly signed by your representative not later than 10/28/2023, Pls. furnish this office the following articles subject to the terms and conditions contained therein.

Instructions :

1. Accomplish this Request for Quotation duly, correctly, and completely.
2. Do not alter the contents of this form in any way.
3. If Technical Specifications/ Terms of Reference is provided, prospect bidder (supplier / service provider) must indicate and signify compliance to every parameter in the specification.

ITEM NO.	DESCRIPTION	QTY.	UNIT	UNIT PRICE
1	LABOR & MATERIALS* : PLS, SEE ATTACHED DRAWING-ABC: PHP 286,945.20 ##### nothing follows #####	1	LOT	P

Date of Delivery: _____
Price Validity : _____
Mode of Payment: _____

Place of Delivery: GSCWD Bodega

****No partial delivery allowed****

Note: 6% WITHHOLDING TAX DEDUCTION

PR NO.: 0923-038

Requested by:

Price quoted by:

GESEM R. CABAÑERO
Supervising Material
Planning Officer

Supplier

Date



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **GSCWD OFFICES FENCE AND STEEL GATES RENOVATION**
 Location: **E. FERNANDEZ ST., BGY. LAGAO, GENERAL SANTOS CITY**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
A	DEMOLITION OF PART OF PERIMETER FENCE AND REMOVAL OF EXISTING STEEL GATE	1	LOT		
	Demolition of Fence and Removal of Steel Gate				
A.1	<i>Demolition of part of Perimeter Fence</i>				
A.2	<i>Removal of Existing Steel Gate</i>				
A.3	<i>Chipping of Concrete Slab to Expose Rebars</i>				
B	SLIDING STEEL GATE FABRICATION AND INSTALLATION	2	NOS.		
B.1	<i>Fabrication and Installation of 75mm x 50mm x 1.5mm Steel Tubular - 6m length for Gate Frame</i>	4	Length		
B.2	<i>Fabrication and Installation of 50mm x 50mm x 1.5mm Steel Tubular - 6m length for Gate Grills</i>	4	Length		
B.3	<i>Fabrication and Installation of G.A. 16 G.I. Plain Sheet - 6m length for Gate Panel</i>	3	Sheets		
B.4	<i>Furnishing and Installation of Steel Gate Roller - V Shape for gate Bottom roller</i>	4	Nos.		
B.5	<i>Furnishing and Installation of Nylon Rollers for gate Top guide</i>	4	Nos.		
B.6	<i>Fabrication and Installation of 75 x 75 x 6mm Angle Bar - 6m length for Runner guide</i>	2	Length		
B.7	<i>Furnishing and Installation of 25mm x 6mm Flat Bar for GI Plain Sheet Stiffener</i>	7	Length		
B.8	<i>Furnishing and Painting of Epoxy Primer and Paint on Steel Gate</i>	1	Gal.		



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
 Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
 E-mail Address: gscwaterdistrict@yahoo.com

Project: **GSCWD OFFICES FENCE AND STEEL GATES RENOVATION**
 Location: **E. FERNANDEZ ST., BGY. LAGAO, GENERAL SANTOS CITY**
 Owner: **GENERAL SANTOS CITY WATER DISTRICT**
 Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
C.1	REBARWORKS	301	KGS		
C.1.1	<i>Furnishing and Installation of Reinforced Concrete Beam with 12mm dia. Def. bars for Main Bar and 10mm dia. Def. bars for Ties</i>				
C.1.2	<i>Furnishing and Installation of Reinforced Concrete Slab at Entrance with 10mm dia. Bars</i>				
C.1.3	<i>Furnishing and Installation of Reinforced Steel on Installed roller guides on columns</i>				
C.1.4	<i>Furnishing and Concreting of Lintel Beam with 10mm dia. Main bars and Stirrups</i>				
C.1.5	<i>Furnishing and Concreting of Planted Columns with 12mm dia. Main bars and 10mm dia. Column Ties</i>				
C.1.6	<i>Furnishing and Concreting of Planted Columns with 12mm dia. Main bars and 10mm dia. Column Ties</i>				
C.1.7	<i>Furnishing and Concreting of Planted Columns with 12mm dia. Main bars and 10mm dia. Column Ties</i>				
C.2	CONCRETE WORKS	4	CU.M.		
C.2.1	<i>Concreting of Slab, Planted Column, Beam Support and Lintel Beams with Class A Concrete Mixture</i>				
D	MASONRY & PLASTERING WORKS	175	SQ.M.		
D.1	<i>Furnishing and Installation of 4" CHB for additional ht. of fence</i>	315	Nos.		



Republic of the Philippines
GENERAL SANTOS CITY WATER DISTRICT

E. Fernandez St. Lagao, General Santos City
Telephone No. (083) 552-3824/ Telefax No. (083) 553-4960
E-mail Address: gscwaterdistrict@yahoo.com

Project: **GSCWD OFFICES FENCE AND STEEL GATES RENOVATION**
Location: **E. FERNANDEZ ST., BGY. LAGAO, GENERAL SANTOS CITY**
Owner: **GENERAL SANTOS CITY WATER DISTRICT**
Subject: **BILL OF QUANTITIES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
D.2	<i>Furnishing and Plastering of Interior and Exterior Wall of fence</i>				
Total Project Cost					

Note:

PLEASE REFER TO APPROVED PLAN FOR FURTHER DETAILS

Submitted by _____ : _____ Date: _____

Name of representative of Bidder _____ : _____

Position: _____ : _____

Name of Bidder _____ : _____